S1 Framing Sections & Details
Bathroom Floor Framing
15 Dow Street, Portland, ME 04102
55-D-12

Inspections Division
Date: 04/07/15

FRAMING

BATH 2

½" = 1'-0"

Note: Use Joist hangers for all connections

- ¾" PLYWOOD FLOORING OVER NEW JOISTS
- ½" CEMENT BOARD
- ¼" TILE

Revised Framing

BATH 2 REPAIR & REFRAME

Sheet 2 of