

QUOTE #	STATUS	CUSTOMER PO#	SHIP DATE
373346	Ordered		See Planned Ship Dates Below
QUOTED BY	TERMS	CONTACT NAME	PROJECT NAME
Judy Hart		Attn:	Reizbaum

- 1 500 Series Hung Double Clipped Corner: 1
- Unit: Wood
  - Operation: Single Hung
  - Profile Type: Ovalo Interior Profiling
  - Unit Size: 29 1/2" x 55" Even Split (Short Side, 46 1/4" ) (Head Length, 12" )
  - Sash: 2 1/16" Head Rail, 3 1/2" Sill Rail, 1 13/16" Stiles
  - Material: Clear Solid Pine
  - Exterior Finish: White (Norcoat)
  - Interior Finish: White (Norcoat)
  - Lower Glass: Dual Pane Sealed Unit [OA Thick 27/32"] @ Ext Pane [3MM Low E 70/36], Int Pane [3MM Clear], Black Spacer (9/16"), Putty (2720) Bead, Argon Fill
  - Upper Glass: Dual Pane Sealed Unit [OA Thick 27/32"] @ Ext Pane [3MM Low E 70/36], Int Pane [3MM Clear], Black Spacer (9/16"), Putty (2720) Bead, Argon Fill
  - Hrdw: Restoration Lock White, No Handle, 2 Locks, White Pan, Balance Type: Lite Lift (Bottom Only), Hidden Tilt Latch, c/w Pan Cover applied with tape
  - Screen: Half Screen, Fiberglass Black Mesh, White; Under Sash Application, Concealed Corner
  - Grille: SDL, 7/8" Putty (598) Ext., 7/8" Ovalo (2640) Int. Bars, , Black Tape
  - Pattern: Rectangular, 2 x 1, 2 Rectangle Lites
  - Exterior Trim: None
  - Interior Trim: None
  - Jamb: 4 9/16"

Overall Unit 29.5" X 55"  
Rough: 30 1/2in X 56in

Opening:  
O.S.M.:

**Planned Ship Date: 8/18/2017**  
Tag: None Assigned

MBC's products are "made-to-order." To achieve MBC's short lead times, we begin production immediately upon your order entry. Therefore, orders cannot be changed and units cannot be returned for credit. Please check this order thoroughly and promptly for errors so MBC can ensure your order was entered as intended.

**Thank you for all of your efforts!**

**TOTAL:**