



MARK	DATE	DESCRIPTION

DATE: 10.22.13
 CHECKED BY: JAD
 DRAWN BY: JAD
 JOB:

SHEET TITLE:
 SCHEDULES

FINISH SCHEDULE					
ROOM NO./ NAME	FLOOR	WALLS	BASE	CILING	NOTES/REMARKS
KITCHENS	KLIK FLR.	PTD. GNB.	N.A.	PTD. GNB.	
BEDROOMS	MD. FLR.	PTD. GNB.	PAINTED 1 X 4 TRIM	PTD. GNB.	
BATHROOMS	CERAMIC TILE	PTD. GNB.	CERAMIC TILE	PTD. GNB.	
LIVING ROOMS	MD. FLR.	PTD. GNB.	PAINTED 1 X 4 TRIM	PTD. GNB.	
UTILITY SPACES	SHEET VINYL	PTD. GNB.	PAINTED 1 X 4 TRIM	PTD. GNB.	

WINDOW SCHEDULE							
MARK	QTY.	MANUFACTURER	MODEL	TYPE	UNIT SIZE	SIZE (R.O.)	REMARKS
A		TO BE DETERMINED	REPLACEMENT-FLR.1	DBL. HUNG REPLACEMENT SASHES	19" x 52" +/- verify in field	EXISTING	2/2 REPLACEMENT SASH -ALUM. 5DL/ PRIMED INTERIOR
B		TO BE DETERMINED	REPLACEMENT-FLR.2	DBL. HUNG REPLACEMENT SASHES	19" x 61" +/- verify in field	EXISTING	2/2 REPLACEMENT SASH -ALUM. 5DL/ PRIMED INTERIOR
C		TO BE DETERMINED	REPLACEMENT-FLR.1	DBL. HUNG REPLACEMENT SASHES	32" x 64" +/- verify in field	EXISTING	2/2 REPLACEMENT SASH -ALUM. 5DL/ PRIMED INTERIOR
D		TO BE DETERMINED	REPLACEMENT-FLR.2	DBL. HUNG REPLACEMENT SASHES	30" x 56" +/- verify in field	EXISTING	2/2 REPLACEMENT SASH -ALUM. 5DL/ PRIMED INTERIOR
E		TO BE DETERMINED	REPLACEMENT-FLR.1	DBL. HUNG REPLACEMENT UNIT	28" x 61" +/- verify in field	EXISTING	NEW 1/1 REPLACEMENT UNIT
F		TO BE DETERMINED	REPLACEMENT-FLR.2	DBL. HUNG REPLACEMENT UNIT	28" x 52" +/- verify in field	EXISTING	NEW 1/1 REPLACEMENT UNIT
G		TO BE DETERMINED	NEW	AWNING	18" X 18"	TBD	BATHROOM VENT AWNING

DOOR SCHEDULE-ALL DOORS WOOD UNLESS NOTED OTHERWISE				ALL NEW & EGRESS DOORS LEVER HANDLED TYPICAL		
MARK	TYPE	LOCATION	MAKE/ MODEL	UNIT SIZE	STYLE	REMARKS
1	1	ALL INTERIOR DOORS		2'-8" x 6'-8"	HINGED	
2	2	ENTRY DOOR AT EXISTING FRONT PORCH		2'-8" x 6'-8"	HINGED	
3	3	OTHER ENTRY DOORS		2'-8" x 6'-8"	HINGED	
4	4	BASEMENT DOOR		2'-8" x 6'-8"	HINGED	2 HR. RATED DOOR
5	1	BATHROOM DOOR		2'-4" x 6'-8"	HINGED	
6	1	CLOSET DOOR		3'-0" x 6'-8"	HINGED	
7	5	CLOSET DOOR		5'-0" x 6'-8"	SLIDER	

