



BASEMENT PLAN
1/4"=1'-0"

- NOTES:**
1. PROVIDE 1 HR. FIRE RATED ENCLOSURE AROUND BOILERS (AS SHOWN) OR PROVIDE SPRINKLER HEAD OFF DOMESTIC WATER ABOVE EACH BOILER. CONTRACTOR TO CONSULT WITH CITY FIRE DEPT. PRIOR TO INSTALLATION OF HEAD TO DETERMINE APPLICABILITY AND ACCEPTABILITY.
 2. ENCLOSURES W/ PLUMBER TO MAINTAIN CLEARANCES TO EQUIPMENT.

- LEGEND**
- ◊ 1 HR. FIRE RATED WALL (SEE DWG. A2)
 - ▨ 1 HR. FIRE RATED CEILING (SEE DWG. A2)
 - ⌬ 1 HR. RATED DOOR W/ 1HR. RATED METAL JAMB (SEE NOTES ON DWG. A0)
 - ⌬ EMERGENCY LIGHT W/ BATTERY BACKUP (SEE NOTES ON DWG. A0)
 - ⊙ SMOKE DETECTOR (HARD WIRED) SEE NOTES ON DWG. A0
 - ⊙ PORTABLE FIRE EXTINGUISHER (SEE NOTES ON DWG. A0)
 - ⊙ EXIST. GAS METER (WALL HUNG)
 - ⊙ EXIST. HOT WATER HEATER

BASEMENT FLOOR PLAN

**ALTERATIONS TO:
RESIDENTIAL UNIT
CONDOMINIUM CONVERSION
9 LARIS STREET
PORTLAND, MAINE 04104**

JOHN H. LEASURE ARCHITECT, INC.
6 Q STREET
SOUTH PORTLAND, MAINE 04106

REV.	DATE	STATUS
0	12/4/06	FOR PERMIT

