CITY OF PORTLAND, MAINE · RESURGAM
Reviewed for Code Compliance
Inspections Division
Approved with Conditions
Date: 06/06/13

LEGEND

- Existing walls to remain
- New exterior walls. See Section, Sheet A–7
- New interior wall. 2x6's @ 16" o.c. faced both sides with 1/2" drywall.

2 / A–8

1 / A–6 FLOOR PLAN – Proposed

Scale: ¼" = 1'–0"

HEATING & COOLING

Contractor to provide split–system heating and cooling unit with the condenser monted on the roof, concealed behind the new parapet wall.

One wall unit located in the Kitchen and one in the Office.

AURORA PROVISIONS
64 Pine Street
Portland, ME

A–6