



1 EXISTING PARTIAL FIRST FLOOR
 SCALE: 1/8" = 1'-0" 0 4' 8' 16'

- Remove as Req'd and/ or Replace Existing Electrical System as Req'd by Code. Electrical System Shall be Design/ Build
- Existing 2" x 10" Floor Joists To Remain
- Remove and replace existing hot water and heating system in there entirety. System Shall be Design/ Build
- Remove all Cabinets, appliances, flooring, etc. Prepare Surfaces for New Finish.
- Bearing Wall to be Removed. Shore and Brace. All other walls shall be verified as being non-load bearing prior to demolition
- Existing Col. to be Removed.
- Existing Beams (2) and Joists (3-Bays) to remain. Shore and Brace.
- Note: G.C. is responsible for Shoring and bracing existing structure to maintain structural integrity. Typ. all Levels as Req'd. Verify all bearing wall conditions prior to demolition. Notify Architect Immediately if additional bearing walls are found where walls are scheduled to be demolished.
- Remove and replace all fixtures and flooring. Prepare Surfaces for New Finish.



PERMIT SET