


CITY OF PORTLAND  
 FIRE PREVENTION BUREAU  
 380 Congress Street, Portland, Maine 04101  
 fireprevention@portlandmaine.gov  
 (207) 874-8400



**NOTICE OF VIOLATION AND ORDER TO CORRECT**

October 12, 2016

<b>Responsible Party 1:</b> Manter Walter P.O. BOX 421 EAST BOOTHBAY, ME 04544		<b>Responsible Party 2:</b> Manter Todd <del>442 ST JOHN ST</del> <i>P.O. BOX 4132</i> PORTLAND, ME <del>04102</del> <i>04101</i>
<b>Location</b> 262 SPRING ST	<b>CBL</b> 056 I013001	<b>Inspection Date</b> 9/22/2016
<b>Inspector</b> Angela Calvo	<b>Inspection Type</b> FP Routine Inspection	<b>Status</b> Failed

*TEMP*  
 New mail address

The City of Portland Fire Department inspected this property, and found the fire and life safety code violations listed below, which you are hereby ordered to correct. You must complete the proposed date of completion column by proposing a reasonable timeframe to remedy each violation. This form must be received by the Fire Prevention Bureau no later than 10/30/2016. The Bureau reserves the right to reject or modify any proposed plan of action, and may require evidence of sufficient financial and technical capacity to complete the proposed plan. Please contact the Bureau with any questions.

**YOUR FAILURE TO SUBMIT A PLAN OF ACTION BY THE DATE PROVIDED, OR TO CORRECT ANY VIOLATION WITHIN THE APPLICABLE TIME FRAME, MAY RESULT IN LEGAL ACTION AGAINST YOU, THE IMPOSITION OF CIVIL PENALTIES, AND THE PURSUIT OF OTHER LEGAL REMEDIES.**

Violation	Proposed Date of Completion
<b>PORTLAND FIRE DEPARTMENT CHAPTER 10 4.6.1, 4.6.2 UNIT/SUITE NUMBERS NOT MARKED;</b> 4.6.1 Residential units shall be designated using numerals. 4.6.2 The first numeral of each residential unit shall be the floor designation. Not all units are numbered on unit doors	<i>11 / 20 / 16</i>
<b>NFPA 101-7.2.4.3.1 FIRE BARRIER REQUIRES MAINTENANCE;</b> Fire barriers separating buildings or areas between which there are horizontal exits shall have a minimum 2-hour fire resistance rating, unless otherwise provided in 7.2.4.4.1, and shall provide a separation that is continuous to the finished grounded level. Missing and cracked sheet rock and plaster in basement stairwell and common hallways.	<i>11 / 20 / 16</i>
<b>NFPA 101- 7.5.1.1 EXIT OBSTRUCTED;</b> Where exits are not immediately accessible from an open floor area, continuous passageways, aisles, or corridors leading directly to every exit shall be maintained and shall be arranged to provide access for each occupant to not less than two exits by separate ways of travel, unless otherwise provided in 7.5.1.1.3 and 7.5.1.1.4. Unit 4 second floor secondary door obstructed with construction material	IMMEDIATELY remove all obstructions from the exits. Your signature below indicates that all obstructions have been removed and will not be replaced.
<b>NFPA 101- 7.5.1.1 AND 7.5.1.1.1 OBSTRUCTED EGRESS;</b> Exits shall be located and exit access shall be arranged so that exits are readily accesible at all times (7.5.1.1). Where exits are not immediately accessible from an open floor area, continuous passageways, aisles, or corridors leading directly to every exit shall be maintained and shall be arranged to provide access for each occupant to not less than two exits by separate ways of travel, unless otherwise provided in 7.5.1.1.3 and 7.5.1.1.4 (7.5.1.1.1). C side fire obstructions	<i>DONE NOW</i> <i>11/20/16</i>

Violation	Proposed Date of Completion
<b>NFPA 101- 7.2.8.5.1 HANDRAILS REQUIRED ON STAIRS;</b> All fire escape stairs shall have walls or guards and handrails on both sides in accordance with 7.2.8.4.1 (b). entry way stair from 1st floor to 2nd floor hand rail needs repair and baulster needed.	11 / 20 / 16
<b>NFPA 101-7.10.5.1 NORMAL ILLUMINATION FOR EXITS;</b> Every sign required by 7.10.1.2, 7.10.1.5, or 7.10.8.1, other than where operations or processes require low lighting levels, shall be suitably illuminated by a reliable light source. Externally and internally illuminated signs shall be legible in both the normal and emergency lighting mode. Lack of lighting in unit hallways; reference 7.5.1.1 in NFPA 101	11 / 20 / 16
<b>NFPA 101- 7.5.1.1.1 SECOND EXIT REQUIRED;</b> Where exits are not immediately accessible from an open floor area, continuous passageways, aisles, or corridors leading directly to every exit shall be maintained and shall be arranged to provide access for each occupant to no less than two exits by separate ways of travel, unless otherwise provided in 7.5.1.1.3 and 7.5.1.1.4. Apartment #5 does not have a second means of egress	12 / 28 / 16 A.S.A.P.
<b>NFPA 1 EXCESSIVE/DISORDERLY STORAGE;</b> Reference NFPA 1 for excessive fuel-load. Construction material in common hallways needs to be removed and excessive debris in the basement needs to be removed.	11 / 20 / 16
<b>NFPA 101- 31.3.2.1.1 BOILER PROTECTION REQUIRED;</b> The areas described in Table 31.3.2.1.1 shall be protected as indicated: Boiler and fuel-fired heater rooms serving more than a single dwelling unit (minimum separation/protection is 1 hour or sprinklers) No sprinkler protection for hot water heaters.	11 / 20 / 16

**VIOLATOR CERTIFICATION**

I agree to remedy the violations listed within the timeframes provided. If I require additional time to comply, I understand that I must contact the Fire Prevention Bureau prior to the deadline to request an extension, which is entirely within the Bureau's discretion to grant or deny.

I further understand that it is my responsibility to schedule a reinspection of my property once the violations have been remedied to do so. My failure to schedule a reinspection shall be deemed an admission that the violations have not been remedied.

If I fail to comply with this agreement, I understand that I am liable for penalties pursuant to the City of Portland Code of Ordinances §§ 1-15 and 10-25, and 30-A M.R.S. § 4452 and may be subject to further legal action.

Date 10/31/16

Responsible Party TODD MAJTER

Date \_\_\_\_\_

Responsible Party \_\_\_\_\_

**SEEN AND AGREED**

Date 10/03/2016

Fire Prevention Bureau Capt. Petruccelli