



CITY OF PORTLAND
 FIRE PREVENTION BUREAU
 380 Congress Street, Portland, Maine 04101
 fireprevention@portlandmaine.gov
 (207) 874-8400

NOTICE OF VIOLATION AND ORDER TO CORRECT

January 16, 2018

PAULINE BARRY
 35 TAYLOR ST
 PORTLAND ME 04102

34 Portland Ave
 Old Orchard Beach ME 04064

Location 35 TAYLOR ST	CBL 057 A003001	Inspection Date 11/29/2017
Inspector Sean Donaghue	Inspection Type FP Routine Inspection	Status Failed

The City of Portland Fire Department inspected this property, and found the fire and life safety code violations listed below, which you are hereby ordered to correct. You must propose a date of completion to remedy each violation, a final date of completion, and a date of re-inspection.

You must send this form to the Fire Prevention Bureau no later than 2/15/2018.

Your failure to submit a plan of action by the date provided, or to correct any violation within the applicable time frame, may result in legal action against you, the imposition of civil penalties, and the pursuit of other legal remedies.

Violation	Proposed Date of Completion
PORTLAND FIRE DEPARTMENT CHAPTER 10 4.6.1, 4.6.2 UNIT/SUITE NUMBERS NOT MARKED; 4.6.1 Residential units shall be designated using numerals. 4.6.2 The first numeral of each residential unit shall be the floor designation. Please number all unit doors, front and back stairwells.	3/1/18
NFPA 101- 7.2.1.8.1 FIRE DOORS MUST BE SELF- OR AUTO-CLOSING; A door leaf normally required to be kept closed shall not be secured in the open position at any time and shall be self-closing or automatic-closing in accordance with 7.2.1.8.2, unless otherwise permitted by 7.2.1.8.3. The existing doors that have a fire rating must be self closing.	7/1/2018
NFPA 101- 7.1.8 STAIR GAURDS MUST BE REPAIRED; Guards in accordance with 7.2.2.4 shall be provided at the open sides of means of egress that exceed 30 inches above the floor or the finished ground level below. Broken bollisters noted between first and second floor in front stairwell and on upper floor. All bollisters must be in place and unbroken. Please repair.	3/1/2018
NFPA 70- ARTICLE 110.12 B EXPOSED WIRING CONNECTIONS; Internal parts of electrical equipment, including busbars, wiring terminals, insulators, and other surfaces, shall not be damaged or contaminated by foreign materials such as paint, plaster, cleaners, abrasives, or corrosive residues. There shall be no damaged parts that may adversely affect safe operation or mechanical strength of the equipment such as parts that are broken; bent; cut; or deteriorated by corrosion, chemical reaction, or overheating. Basement near base of stairs	complete 2-10-18
NFPA 70 MISSING BOX COVERS; Refer to NFPA 70, National Electrical Code, on standards for missing box covers. Open junction boxes in basement require covers.	complete 2/10-18

Violation	Proposed Date of Completion
NFPA 70 MISSING BREAKER IN PANEL; Refer to NFPA 70, National Electrical Code, for information on missing breakers in an electrical panel. Old fuse electrical panel in basement may not be connected, please either remove or fill holes in panel if still connected.	complete 2-7-18
NFPA 101- 31.3.2.1.1 BOILER PROTECTION REQUIRED; The areas described in Table 31.3.2.1.1 shall be protected as indicated: Boiler and fuel-fired heater rooms serving more than a single dwelling unit (minimum separation/protection is 1 hour or sprinklers) Boilers and gas hot water heaters in basement require sprinkler coverage.	2/11/18
NFPA 101- 8.3.4.2 60 MINUTE FIRE DOOR REQUIRED; Refer to NFPA 101- Table 8.3.4.2 that states fire door assemblies for vertical shafts (including stairways, exits, and refuse chutes) are rated and required for 1 hour. Basement and most unit doors aren't fire rated doors. All interior doors must have proper fire rating. Existing solid doors possibly may meet fire rating requirement but would have to be certified, otherwise they will require replacement as well.	2/11/18
FINAL DATE OF COMPLETED VIOLATION(S)	2/11/18
FIRE PREVENTION BUREAU RE-INSPECTION OF COMPLETED VIOLATION(S)	2/11/18

The Bureau reserves the right to reject or modify any proposed plan of action, and may require evidence of sufficient financial and technical capacity to complete the proposed plan. Please contact the Bureau with any questions.

VIOLATOR CERTIFICATION

I agree to remedy the violations listed within the timeframes provided. If I require additional time to comply, I understand that I must contact the Fire Prevention Bureau prior to the deadline to request an extension, which is entirely within the Bureau's discretion to grant or deny.

I further understand that it is my responsibility to schedule a reinspection of my property once the violations have been remedied to do so. My failure to schedule a reinspection shall be deemed an admission that the violations have not been remedied.

If I fail to comply with this agreement, I understand that I am liable for penalties pursuant to the City of Portland Code of Ordinances §§ 1-15 and 10-25, and 30-A M.R.S. § 4452 and may be subject to further legal action.

2-10-18 _____
Date Responsible Party
Rebecca Parry

Date Responsible Party

SEEN AND AGREED

2/14/18 _____
Date Fire Prevention Bureau
Capt. [Signature]

