

Sales Person:



Customer Acknowledgement
Quote Date 12/7/2018
Date Ordered 12/7/2018



Dealer Name:

149120 EDWARD L CARIGNAN & SONS -

Bill To:

Ship To:

Reviewed for Code Compliance  
Permitting and Inspections Department  
Approved with Conditions

01/23/2019

Phone: (207) 252-8577 Fax: 207-892-5856

Order Notes:

Delivery Notes:

Quote Name:


Project Name:

may st

may st

QUOTE #	RUSH	STATUS	PO#
2042042	No	Ordered	

Line Item #	Qty	Width x Height	UI	Description
1	1	29" X 41.5"	71	




0171-New Construction Left 29 x 41.5  
 Operation / Venting = Left  
 New Construction With J-Channel  
 Frame Color = White  
 CLIMATECH, No Upgrade  
 Egress Hardware  
 U-Factor = 0.28, CR = 59, SHGC = 0.28, VT = 0.5, CPD =  
 ASO-A-31-04063-00001  
 No Jamb Extension, NC Wrapping, Frame Size  
**Line Item Notes:**

Comment / Room:

None Assigned

Line Item #	Qty	Width x Height	UI	Description
2	1	29" X 41.5"	71	

Overall Rough Opening: 29.5" X 42"



0171-New Construction Right 29 x 41.5  
 Operation / Venting = Right  
 New Construction With J-Channel  
 Frame Color = White  
 CLIMATECH, No Upgrade  
 Egress Hardware  
 U-Factor = 0.28, CR = 59, SHGC = 0.28, VT = 0.5, CPD =  
 ASO-A-31-04063-00001  
 No Jamb Extension, NC Wrapping, Rough Opening  
**Line Item Notes:**

Comment / Room:

None Assigned

QUOTE #	RUSH	STATUS	PO#
2042042	No	Ordered	

**Customer Notes:**

Total Unit Count	2
------------------	---

**ATTENTION**

Please note that all weights provided are estimates and subject to change based on actual order shipment.  
 For Informational Purposes: All windows are viewed from the outside looking in.


**NOTICE:** The rating information provided on this quote is based upon the NFRC ratings at the time of quote. Such ratings are subject to changes in the standard by the applicable regulatory agencies and will be finalized at the time of manufacturing. All ratings printed on the NFRC label will supersede the NFRC rating set forth in the quote. Any changes made to an order after submission may also result in changes to the NFRC rating. Customer shall be solely responsible for determining whether the product ordered meets their jurisdiction's requirements.



Reviewed for Code Compliance  
 Permitting and Inspections Department  
 Approved with Conditions

**01/23/2019**

In accordance with the state of California:

 **WARNING:** Cancer and Reproductive Harm - [www.p65Warnings.ca.gov](http://www.p65Warnings.ca.gov)

This order is subject to AMI's Standard Terms and Conditions, which can be found here:  
<http://www.associatedmaterials.com/Tools.html>

I have reviewed this order and certify that it is correct. I understand that this order is noncancellable, nonreturnable, and nonrefundable.

By \_\_\_\_\_ Authorized Representative



01/23/2019

## Select Model

(Model 0171)	0171
New Const. Single Vent Casement	
Sash Width	27.3750
Sash Height	39.8750
Glass Width	24.3750
Glass Height	36.8750
Screen Width	24.9375
Screen Height	37.5000
Egress Opening Width (Standard Hinge)	17.7500
Egress Opening Height (Standard Hinge)	37.1250
Egress Opening Area w/Standard Hinge (sq.ft.)	4.5762
Egress Opening Width (Egress Hinge)	22.1875
Egress Opening Height (Egress Hinge)	37.1250
Egress Opening Area w/Egress Hinge (sq.ft.)	5.7202

Min. W: 16	Max W: 36	
Min. H: 19	Max H: 78	Max UI: 114

Exact Size	
Width:	29
Height:	41.5

Opening:	Exact Size	<< Select Opening
Type:	Standard	
Screen:		
Glass:	Double Strength (3 mm)	

 Add Grid for Weight Calculation

 AC Sash Calculator