



© 2017 RYAN SENATORE ARCHITECTURE

LITTLE GIANT RESTAURANT
 211 DANFORTH STREET
 PORTLAND, MAINE



RYAN SENATORE
 ARCHITECTURE
 666 CONGRESS STREET
 PORTLAND, MAINE 04101
 207-650-6414
 senatorearchitecture.com

CONSULTANTS:

REVISIONS:
 ▲ REVISION #1 - 03 / 01 / 17

DATE: FEBRUARY 24, 2017

PROJECT No. 1640

DRAWN BY: RRT, RJS

CHECKED BY: RJS

SCALE: AS NOTED

SHEET TITLE:

**WALL TYPES
 AND
 ASSEMBLIES**

A0-1

GRAPHIC DEPICTION		DESCRIPTION											
		<ul style="list-style-type: none"> - LAYER OF 5/8" TYPE-X GWB - 3-5/8" METAL STUDS AT 16" O.C. - 3-1/2" ACOUSTICAL FIRE BATT INSULATION - LAYER OF 5/8" TYPE-X GWB 											
		<table border="1"> <thead> <tr> <th>TYPE</th> <th>FIRE RATING</th> <th>UL NUMBER</th> <th>STC RATING</th> <th>IIC RATING</th> </tr> </thead> <tbody> <tr> <td>1A</td> <td>1 HR</td> <td>U311</td> <td>N/A</td> <td>N/A</td> </tr> </tbody> </table>				TYPE	FIRE RATING	UL NUMBER	STC RATING	IIC RATING	1A	1 HR	U311
TYPE	FIRE RATING	UL NUMBER	STC RATING	IIC RATING									
1A	1 HR	U311	N/A	N/A									

GRAPHIC DEPICTION		DESCRIPTION											
		<ul style="list-style-type: none"> - LAYER OF 5/8" GWB - 3-5/8" METAL STUDS AT 16" O.C. - 3-1/2" SOUND BATT INSULATION - LAYER OF 5/8" GWB 											
		<table border="1"> <thead> <tr> <th>TYPE</th> <th>FIRE RATING</th> <th>UL NUMBER</th> <th>STC RATING</th> <th>IIC RATING</th> </tr> </thead> <tbody> <tr> <td>NA</td> <td>N/A</td> <td>N/A</td> <td>35-39</td> <td>N/A</td> </tr> </tbody> </table>				TYPE	FIRE RATING	UL NUMBER	STC RATING	IIC RATING	NA	N/A	N/A
TYPE	FIRE RATING	UL NUMBER	STC RATING	IIC RATING									
NA	N/A	N/A	35-39	N/A									

GRAPHIC DEPICTION		DESCRIPTION											
		<ul style="list-style-type: none"> - LAYER OF 5/8" TYPE-X GWB - EXISTING STUDS TO REMAIN - 3-1/2" ACOUSTICAL FIRE BATT INSULATION - LAYER OF 5/8" TYPE-X GWB 											
		<table border="1"> <thead> <tr> <th>TYPE</th> <th>FIRE RATING</th> <th>UL NUMBER</th> <th>STC RATING</th> <th>IIC RATING</th> </tr> </thead> <tbody> <tr> <td>1B</td> <td>1 HR</td> <td>U311</td> <td>N/A</td> <td>N/A</td> </tr> </tbody> </table>				TYPE	FIRE RATING	UL NUMBER	STC RATING	IIC RATING	1B	1 HR	U311
TYPE	FIRE RATING	UL NUMBER	STC RATING	IIC RATING									
1B	1 HR	U311	N/A	N/A									

GRAPHIC DEPICTION		DESCRIPTION											
		<ul style="list-style-type: none"> - LAYER OF 5/8" GWB - 3-5/8" METAL STUDS AT 16" O.C. - LAYER OF 5/8" GWB 											
		<table border="1"> <thead> <tr> <th>TYPE</th> <th>FIRE RATING</th> <th>UL NUMBER</th> <th>STC RATING</th> <th>IIC RATING</th> </tr> </thead> <tbody> <tr> <td>NB</td> <td>N/A</td> <td>N/A</td> <td>N/A</td> <td>N/A</td> </tr> </tbody> </table>				TYPE	FIRE RATING	UL NUMBER	STC RATING	IIC RATING	NB	N/A	N/A
TYPE	FIRE RATING	UL NUMBER	STC RATING	IIC RATING									
NB	N/A	N/A	N/A	N/A									

GRAPHIC DEPICTION		DESCRIPTION											
		<ul style="list-style-type: none"> - (2) LAYERS OF 5/8" TYPE-X GWB - 2X6 WOOD STUDS AT 16" O.C. - 5-1/2" ACOUSTICAL FIRE BATT INSULATION - (2) LAYERS OF 5/8" TYPE-X GWB 											
		<table border="1"> <thead> <tr> <th>TYPE</th> <th>FIRE RATING</th> <th>UL NUMBER</th> <th>STC RATING</th> <th>IIC RATING</th> </tr> </thead> <tbody> <tr> <td>2A</td> <td>2 HR</td> <td>U419</td> <td>N/A</td> <td>N/A</td> </tr> </tbody> </table>				TYPE	FIRE RATING	UL NUMBER	STC RATING	IIC RATING	2A	2 HR	U419
TYPE	FIRE RATING	UL NUMBER	STC RATING	IIC RATING									
2A	2 HR	U419	N/A	N/A									

GRAPHIC DEPICTION		DESCRIPTION											
		<ul style="list-style-type: none"> - LAYER OF 5/8" TYPE-X GWB - 2X6 WOOD STUDS AT 16" O.C. - 5-1/2" ACOUSTICAL FIRE BATT INSULATION - LAYER OF 5/8" TYPE-X GWB 											
		<table border="1"> <thead> <tr> <th>TYPE</th> <th>FIRE RATING</th> <th>UL NUMBER</th> <th>STC RATING</th> <th>IIC RATING</th> </tr> </thead> <tbody> <tr> <td>1C</td> <td>1 HR</td> <td>U311</td> <td>N/A</td> <td>N/A</td> </tr> </tbody> </table>				TYPE	FIRE RATING	UL NUMBER	STC RATING	IIC RATING	1C	1 HR	U311
TYPE	FIRE RATING	UL NUMBER	STC RATING	IIC RATING									
1C	1 HR	U311	N/A	N/A									

GRAPHIC DEPICTION		DESCRIPTION											
		<ul style="list-style-type: none"> - LAYER OF 5/8" GWB - 2X6 WOOD STUDS AT 16" O.C. - 5-1/2" SOUND BATT INSULATION - LAYER OF 5/8" GWB 											
		<table border="1"> <thead> <tr> <th>TYPE</th> <th>FIRE RATING</th> <th>UL NUMBER</th> <th>STC RATING</th> <th>IIC RATING</th> </tr> </thead> <tbody> <tr> <td>NC</td> <td>N/A</td> <td>N/A</td> <td>35-39</td> <td>N/A</td> </tr> </tbody> </table>				TYPE	FIRE RATING	UL NUMBER	STC RATING	IIC RATING	NC	N/A	N/A
TYPE	FIRE RATING	UL NUMBER	STC RATING	IIC RATING									
NC	N/A	N/A	35-39	N/A									

GRAPHIC DEPICTION		DESCRIPTION											
		<ul style="list-style-type: none"> - (2) LAYERS OF 5/8" TYPE-X GWB - EXISTING GWB - EXISTING STUDS - EXISTING GWB - (2) LAYERS OF 5/8" TYPE-X GWB 											
		<table border="1"> <thead> <tr> <th>TYPE</th> <th>FIRE RATING</th> <th>UL NUMBER</th> <th>STC RATING</th> <th>IIC RATING</th> </tr> </thead> <tbody> <tr> <td>2B</td> <td>2 HR</td> <td>SIM. U419</td> <td>N/A</td> <td>N/A</td> </tr> </tbody> </table>				TYPE	FIRE RATING	UL NUMBER	STC RATING	IIC RATING	2B	2 HR	SIM. U419
TYPE	FIRE RATING	UL NUMBER	STC RATING	IIC RATING									
2B	2 HR	SIM. U419	N/A	N/A									

GRAPHIC DEPICTION		DESCRIPTION											
		<ul style="list-style-type: none"> - LAYER OF 5/8" TYPE-X GWB - EXISTING STUDS TO REMAIN - 5-1/2" ACOUSTICAL FIRE BATT INSULATION - LAYER OF 5/8" TYPE-X GWB 											
		<table border="1"> <thead> <tr> <th>TYPE</th> <th>FIRE RATING</th> <th>UL NUMBER</th> <th>STC RATING</th> <th>IIC RATING</th> </tr> </thead> <tbody> <tr> <td>1D</td> <td>1 HR</td> <td>U311</td> <td>N/A</td> <td>N/A</td> </tr> </tbody> </table>				TYPE	FIRE RATING	UL NUMBER	STC RATING	IIC RATING	1D	1 HR	U311
TYPE	FIRE RATING	UL NUMBER	STC RATING	IIC RATING									
1D	1 HR	U311	N/A	N/A									

GRAPHIC DEPICTION		DESCRIPTION											
		<ul style="list-style-type: none"> - LAYER OF 5/8" GWB - 2X6 WOOD STUDS AT 16" O.C. - LAYER OF 5/8" GWB 											
		<table border="1"> <thead> <tr> <th>TYPE</th> <th>FIRE RATING</th> <th>UL NUMBER</th> <th>STC RATING</th> <th>IIC RATING</th> </tr> </thead> <tbody> <tr> <td>ND</td> <td>N/A</td> <td>N/A</td> <td>35-39</td> <td>N/A</td> </tr> </tbody> </table>				TYPE	FIRE RATING	UL NUMBER	STC RATING	IIC RATING	ND	N/A	N/A
TYPE	FIRE RATING	UL NUMBER	STC RATING	IIC RATING									
ND	N/A	N/A	35-39	N/A									