Inspections Division
Date: 09/10/13

BUILDING "A" NUMBERED CALL OUTS :

1. DEMOLISH EXISTING TRASH ROOM CONCRETE WALLS AND PARTITION WALL AND DOORWAY.
2. INSTALL 8' WIDE OVERHEAD DOOR IN CMU WALL. PROVIDE 3"x3"x3/8" STEEL ANGLE LINTEL OR BETTER FOR OPENING. BOTTOM OF DOOR OPENING TO BE FLUSH WITH NEW FLOOR SLAB. CUT FOUNDATION WALL AS NEEDED.
3. EXCAVATE AREA AND INSTALL 6" REINFORCED CONCRETE SLAB AT SAME ELEVATION AS EXISTING TRASH ROOM FLOOR, (94" CEILING HEIGHT). SLOPE TO FLOOR DRAIN. UNDERPIN PERIMETER BUILDING FOOTINGS AS NEEDED.
4. PROVIDE 36" STEEL DOOR AND FRAME TO REPLACE EXISTING.
5. INSTALL 6" REINFORCED CONCRETE APRON SLAB UP TO EXISTING ASPHALT PARKING AREA . SLOPE TO PARKING AREA AND FLUSH WITH INTERIOR SLAB.
6. INSTALL 6" REINFORCED CONCRETE DUMPSTER PAD. SLOPE 1/8" PER FOOT AWAY FROM BUILDING. MATCH EXISTING ASPHALT PARKING SURFACE.
7. PROVIDE AND INSTALL MARATHON MINI-MAC (R) TRASH COMPACTOR. REFER TO SPECIFICATIONS.
8. REROUTE SEWER MAIN AND PIPING ALONG REAR FOOTING / WALL. INSTALL NEW 24" MOP SINK WITH HOT AND COLD WATER NEAR COMPACTOR AREA.
9. ADD FIRE SPRINKLER PIPING AND NEW HEADS TO PROVIDE FULL COVERAGE FOR THE ENLARGED ROOM.
10. ADD NEW 4" DIAMETER FLOOR DRAIN WITH PIPING TO EXISTING FLOOR DRAIN.
11. INSTALL ADDITIONAL HIGHT FIXTURE TO MATCH EXISTING AND WIRE TO EXISTING SWITCH.

GROUND FLOOR PARTIAL PLAN – BLDG. "C"
SCALE : 1/4" = 1'-0"

0' 5' 10'

CURRENT ISSUE STATUS: ISSUED FOR BID 09/18/07	Danforth Heights Trash Handling Improvements	CRITERIUM ENGINEERS 22 MONUMENT SQUARE SUITE 300 PORTLAND, ME 04101 TEL 207-775-1969 800-922-1969 FAX 207-775-4415	SHEET TITLE: GROUND FLOOR PLAN BLDG. "C"

SCALE: AS NOTED	DATE: 08-24-07
PROJECT MANAGER: RM	SHEET No.
ENGINEER OF RECORD: RM	A-4
PROJECT No. 07-233	