PROJECT: NEW YARD
SUBJECT: OPERATIONS BUILDING
ITEM: Column Pier Details

GAGNON ENGINEERING INC.
Structural Consultants

DATE: 07/11/14
BY: RG
SHEET: 5 OF 9
PROJECT NO. 402

Reviewed for Code Compliance
Inspections Division
Approved with Conditions
Date: 08/28/14

COLUMN PIER (typ UNO)

Scale: $\frac{3}{4}$" = 1'-0"

Note: Extend vertical Bars 27" into Gr Bm UNO

#6 Vert. Bars
#4 Ties @ 6" (dbl @ top)

PIER REBAR (typ UNO)

1'-2" UNO

CORNER PIER (typ UNO)

Scale: $\frac{3}{4}$" = 1'-0"

STATE OF MAINE
ROGER R. GAGNON
No. 3409
LICENSED
PROFESSIONAL ENGINEER