



BUYER ACCEPTANCE SIGN AND DATE

- NOTES
- Fireblocking shall be installed at the floor and ceiling level. Fireblocking material shall be as permitted in Indiana Building Code Exterior joints in the building envelope that are sources of air leakage, such as floor and ceiling lines, door and windows, or any other penetrations through the building envelope shall be caulked, gasketed, weather-stripped, wrapped or otherwise sealed to limit uncontrolled air movement. Stopping materials installed on-site are subject to local review, approval and inspection.
  - In all framed walls, floors and roof/ceiling comprising elements of the building thermal envelope, a vapor retarder shall be installed on the warm-in-winter side of the insulation with the following exceptions:
    - Where the framed cavity or space is ventilated to allow moisture to escape.
  - Where required, the vapor retarder shall be comprised of any material (kraft backing, polyethylene, spray applied) approved for such use and having a perm rating of 1 or less.
  - Additional connections per standard construction manual or calculations package

REVISIONS:	SCALE: 1/2" = 1'-0"	APPROVED BY:	<b>Twin Modular Services Inc.</b> Blackwood, NJ	TITLE: CROSS SECTION	JOB NO: TMS032212-19
	DATE: 03/26/2012	DRAWN BY: R. Knowles		MODEL: 812 GUARD BOOTH	DRAWING NO: 5

0110.1150 2008-12-02