Reviewed for Code Compliance
Inspections Division
Approved with Conditions

Date: 10/03/14

ENDWALL FRAMING: FRAME LINE 1

ENDWALL FRAMING: FRAME LINE 6

A 6 CORNER DETAIL

ERECTOR NOTE:
EXP. EW RAFTER ARE TO BE FIELD DRILLED WITH 9/16 HOLES FOR 1/2 X 1-1/4 A325 BOLTS

B 6 SECTION

C 6 SECTION

| QTY | PART MARK | DESCRIP | LENGTH |
|---|---|---|---|
| 13 | G1 | 10Z35 12 | 28' 1-1/2 |
| 2 | G2 | 10Z35 12 | 5' 4 |
| 6 | G3 | 10Z35 14 | 5' 3-1/2 |
| 16 | G4 | 10Z35 14 | 4' 3-3/8 |
| 7 | G5 | 10Z35 14 | 3' 8 |
| 4 | G6 | 10Z35 12 | 19' 11-1/2 |
| 6 | G7 | 10Z35 12 | 25' 8 |
| 5 | G8 | 10Z35 14 | 19' 1-1/2 |
| 6 | G9 | 10Z35 14 | 8' 10 |
| 4 | G10 | 10Z35 14 | 15' 11-1/2 |
| 5 | G11 | 10Z35 14 | 2' 0 |
| 2 | G12 | 10Z35 14 | 14' 10 |
| 3 | G33 | 10Z25 14 | 15' 7-1/2 |
| 3 | G34 | 10Z35 12 | 27' 9-1/2 |
| 1 | G35 | 10Z25 12 | 25' 7-1/2 |
| 2 | G36 | 10Z35 12 | 25' 3-1/2 |
| 3 | G55 | 10Z35 12 | 18' 8-1/2 |
| 1 | J1 | 10C25 12 | 37' 7 |
| 1 | J2 | 10C25 12 | 43' 7 |
| 1 | J3 | 10C25 12 | 36' 2 |
| 1 | J4 | 10C25 12 | 41' 0 |
| 1 | H1 | 10C25 12 | 19' 11-1/2 |
| 1 | H2 | 10C25 12 | 15' 11-1/2 |
| 2 | BC14 | 10C25 16 | 24' 11-1/2 |
| 1 | BC15 | 10C25 16 | 29' 3-3/4 |
| 1 | BC16 | 10C25 16 | 8' 0-3/4 |
| 1 | BC17 | 10C25 16 | 21' 9 |
| 1 | BC18 | 10C25 16 | 1' 9 |

STATE OF MAINE
STEPHEN JON REIFENBERG
NO. 4763
LICENSED
PROFESSIONAL ENGINEER

9/17/14

ERECTION REQUIRES MINOR ADJUSTMENTS

ESSEX STRUCTURAL STEEL CO., INC.
CORTLAND, NEW YORK 13045

REVISIONS

PROJECT: CANAL LANDING
100 WEST COMMERCIAL STREET
PORTLAND, MAINE 04101

CONTRACTOR: IRISHSPAN INDUSTRIES

PROJECT NO.: S-1468

TITLE: ENDWALL FRAMING PLAN

SHEET: 6

DRAWN BY: JCK | DATE: 7/1/14 | SCALE: C.N.S.