Reviewed for Code Compliance
Inspections Division
Approved with Conditions

Date: 10/03/14

SIDEWALL FRAMING: FRAME LINE A

SIDEWALL FRAMING: FRAME LINE M

SIDEWALL FRAMING: FRAME LINE J

QTY	PART MARK	DESCRIP	LENGTH
5	G21	12Z35 12	32' 7
8	G22	12Z35 12	23' 11-1/2
9	G23	12Z35 12	5' 2-1/2
5	G24	12Z35 12	11' 11-1/2
4	G25	12Z35 12	14' 8
5	G26	12Z35 12	32' 1-1/2
10	G27	12Z35 12	34' 3-1/2
5	G28	12Z35 12	33' 3-1/2
10	G29	12Z35 12	10' 10
4	G30	12Z35 12	5' 7
4	G31	12Z35 12	1' 7
5	G52	12Z35 12	3' 2-1/2
5	G53	12Z35 12	7' 2-1/2
1	G54	12Z35 12	3' 9
1	G51	12Z35 12	19' 11-1/2
8	J7	12C35 12	30' 5-3/16
4	J8	12C35 12	22' 10-1/2
2	J9	12C25 12	30' 5-3/16
1	H8	12C35 12	19' 11-1/2
4	H3	12C35 12	23' 11-1/2

QTY	PART MARK	DESCRIP	LENGTH
8	PFC3	WEB: 14-3/4" X 3/16" FLG.: 8" X 5/8"	29' 10-5/8
4	PFR2	WEB: 15" X 3/16" FLG.: 8" X 1/2"	27' 3-11/16

QTY	PART MARK	DESCRIP	LENGTH
3	BC1	12C25 16	29' 11-1/2
1	BC2	12C25 16	31' 1-1/2
2	BC3	12C25 16	8' 9
1	BC4	12C25 16	14' 8
2	BC5	12C25 16	5' 4-1/2
1	BC6	12C25 16	32' 8
1	BC7	12C25 16	1' 8
1	BC8	12C25 16	5' 8
1	BC25	12C25 16	3' 4-1/2
1	BC26	12C25 16	7' 4-1/2
2	H4	12C25 12	11' 11-1/2

STATE OF MAINE
STEPHEN JON REIFENBERG
NO. 4763
LICENSED
PROFESSIONAL ENGINEER

9/17/14

ERECTION REQUIRES MINOR ADJUSTMENTS

ESSEX STRUCTURAL STEEL CO., INC.
CORTLAND, NEW YORK 13045

REVISIONS

PROJECT: CANAL LANDING
100 WEST COMMERCIAL STREET
PORTLAND, MAINE 04101
CONTRACTOR: IRISHSPAN INDUSTRIES
PROJECT NO.: S-1468

TITLE: SIDEWALL FRAMING PLAN

SHEET: 5

DRAWN BY: JCK | DATE: 7/1/14 | SCALE: D.N.S.