Reviewed for Code Compliance
Inspections Division
Approved with Conditions

Date: 10/03/14

NOTE:
USE C-5 TO ATTACH
JAMB/GIRTS ABOVE PORTAL

SIDEWALL FRAMING: FRAME LINE C

SIDEWALL FRAMING: FRAME LINE I

QTY	PART MARK	DESCRIP	LENGTH
4	CB10	1" ROD	10' 9
4	CB11	1" ROD	12' 2
16	CB12	1" ROD	15' 0
8	G13	8Z25 14	26'11-1/2
6	G14	8Z25 14	28' 7-1/2
12	G15	8Z25 14	19' 11-1/2
12	G16	8Z25 14	3' 3-3/4
18	G17	8Z25 14	4' 0
6	G18	8Z25 14	7' 0
6	G19	8Z25 14	1' 0
7	G20	8Z25 14	25' 9-9/16
2	G56	8Z25 14	28' 1-1/ 2
6	G57	8Z25 14	3' 6
4	J5	8C25 12	16' 3-3/4
4	J6	8C25 12	37' 2-1/4
2	J10	8C25 12	11' 0-1/2
4	J13	8C25 12	19' 2
4	J14	8C25 14	7' 2-1/4
4	H5	8C25 12	19' 11-1/2
2	H9	8C25 14	3' 4
2	SH1	8C25 12	9' 11-1/2
1	BC9	8C25 16	27' 6-7/8
6	BC10	8C25 16	4' 1-3/4
1	BC11	8C25 16	7' 1-3/4
1	BC12	8C25 16	1' 1-3/4
1	BC13	8C25 16	25' 9-1/2

FOR ROD USE (2) CB12 (15'-0") ROD & COUPLERS PER ASSEMBLY

STATE OF MAINE
STEPHEN JON REIFENBERG
NO. 4763
LICENSED
PROFESSIONAL ENGINEER

9/17/14

ERECTION REQUIRES MINOR ADJUSTMENTS

QTY	PART MARK	DESCRIP	LENGTH
4	PFC1	WEB: 15" X 3/16" FLG.: 8" X 1/2"	17' 6
4	PFC2	WEB: 15" X 3/16" FLG.: 8" X 1/2"	15' 2
4	PFR1	WEB: 19 1/4" X 3/16" FLG.: 10" X 3/8"	27' 3-1/2

ESSEX STRUCTURAL STEEL CO., INC.
CORTLAND, NEW YORK 13045

REVISIONS

PROJECT: CANAL LANDING
100 WEST COMMERCIAL STREET
PORTLAND, MAINE 04101
CONTRACTOR: IRISHSPAN INDUSTRIES
PROJECT NO.: S-1468

TITLE: LINE C, I FRAMING PLAN

SHEET: 5B

DRAWN BY: JCK | DATE: 7/1/14 | SCALE: D.N.S.