Reviewed for Code Compliance
Inspections Division
Approved with Conditions

Date: 11/19/13

NEW YARD LLC
120'-0" x 160'-6"

40 WEST COMMERCIAL STREET
PORTLAND, ME 04107

STATE OF MAINE
DWAYNE R. MOENCH
19559
LICENSED
PROFESSIONAL ENGINEER
11-13-13

ABBREVIATION LEGEND			
MARK	DESCRIPTION	MARK	DESCRIPTION
P	PURLIN	ITS	INCLUSIVE TENSION SYSTEM
CB	CABLE BRACE	EC	END WALL COLUMN
S	SUPPORT PURLIN	G	GIRT
FB	FLANGE BRACE	DJ	DOOR JAMB
SP	SPLICE PLATE	DH	DOOR HEADER
b	ATTACHMENT CLIP	VF	VENT FRAME

S0	INDEX & COVER PAGES
	S0.0 - SHEET INDEX
	S0.1 - BUILDING SPECS.
	S0.2 - ANCHOR BOLT REACTIONS
	S0.3 - 3D VIEW 1
	S0.4 - 3D VIEW 2
S1	ANCHOR BOLT LAYOUT
	S1.0 - ANCHOR BOLT PLAN
	S1.1 - ANCHOR BOLT DETAILS
S2	RIGID FRAME SECTIONS
	S2.0.0 - EXTRUSION LAYOUT & RIGGING DETAILS
	S2.0.1 - EXTRUSION LAYOUT & RIGGING DETAILS
	S2.0.2 - EXTRUSION LAYOUT & RIGGING DETAILS
	S2.1 - RIGID FRAME PROFILE FRAME LINE 1 @ BAY 1
	S2.2 - RIGID FRAME PROFILE FRAME LINES 2-4, 6-8 @ BAYS 2, 3, 6 & 7
	S2.3 - RIGID FRAME PROFILE FRAME LINES 4-6 @ BAYS 4 & 5
	S2.4 - RIGID FRAME PROFILE FRAME LINE 9 @ BAY 8
	S2.6 - PURLIN CONNECTION DETAILS
S3	RIGID FRAME LAYOUT
	S3.0 - ROOF FRAMING PLAN
	S3.1 - SIDE WALL FRAMING PLAN
	S3.7 - SIDE WALL FRAMING DETAILS
S4	END WALL FRAMING
	S4.0 - GRID 1 FRAMING PLAN
	S4.1 - GRID 9 FRAMING PLAN
	S4.4 - ENDWALL DETAILS
	S4.5 - ENDWALL DOOR FRAMING DETAILS
S5	COMPONENT DETAILS
	S5.0 - CLIP DETAILS
S6	FABRIC DETAILS
	S6.0 - FABRIC LAYOUT
	S6.1 - FABRIC DETAILS
S7	LINER DETAILS
	S7.0 - ROOF LINER FABRIC LAYOUT
	S7.1 - LINER DETAILS

LEGACY BUILDING SOLUTIONS
www.LegacyBuildingSolutions.com
1-877-259-1022

NEW YARD LLC
120'-0" x 160'-6"
PORTLAND, ME

Legacy Building Solutions
19500 County Rd 142
South Haven, MN 55830
p. 320-259-7126

PATENT PENDING

SHEET INDEX

S0.0