GENERAL NOTES

- 1. IN ADDITION TO THESE PLANS AND NOTES, THE CONTRACTOR SHALL REFER TO THE PROJECT MANUAL FOR CONSTRUCTION SPECIFICATIONS AND BIDDING
- THIS PROJECT WILL BE SUBJECT TO THE TERMS AND CONDITIONS OF ALL PERMITS ISSUED BY THE MAINE DEPARTMENT OF ENVIRONMENTAL PROTECTION,
- THE U.S DEPARTMENT OF THE ARMY CORPS OF ENGINEERS, LOCAL UTILITY COMPANIES AND THE CITY OF PORTLAND.

 3. THE CONTRACTOR SHALL REFER TO THE ARCHITECTURAL PLANS FOR EXACT LOCATIONS AND DIMENSIONS OF THE ENTRANCE, PAVING, PRECISE BUILDING DIMENSIONS, AND EXACT BUILDING UTILITY ENTRANCE POINTS. ENTRANCES IN MOST LOCATIONS REQUIRE STRUCTURAL SLABS. REFER TO THE
- 4. ALL REQUIRED AND NECESSARY INSPECTIONS AND OR CERTIFICATIONS REQUIRED BY CODES AND/OR UTILITY SERVICE COMPANIES SHALL BE PERFORMED PRIOR TO ANNOUNCED BUILDING POSSESSIONS AND THE FINAL SERVICE CONNECTIONS.

ARCHITECTURAL AND STRUCTURAL DRAWINGS FOR INFORMATION ON THE STRUCTURAL SLAB ENTRANCES.

- 5. THE CONTRACTOR IS SPECIFICALLY CAUTIONED THAT THE LOCATION AND/OR THE ELEVATION OF THE EXISTING UTILITIES AS SHOWN ON THESE PLANS IS BASED ON RECORDS OF THE VARIOUS UTILITY COMPANIES AND, WHERE POSSIBLE, MEASUREMENTS TAKEN IN THE FIELD. THIS INFORMATION IS NOT TO BE RELIED ON AS BEING EXACT OR COMPLETE. THE CONTRACTOR MUST CALL THE APPROPRIATE UTILITY COMPANY AND DIG SAFE AT LEAST 72 HOURS PRIOR TO ANY EXCAVATION TO REQUEST EXACT FIELD LOCATION OF UTILITIES. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO RELOCATE ALL EXISTING UTILITIES WHICH CONFLICT WITH THE PROPOSED IMPROVEMENTS SHOWN ON THE PLANS, AT ITS SOLE COST.
- 6. MAINTENANCE OF EROSION CONTROL MEASURES IS OF PARAMOUNT IMPORTANCE TO THE APPLICANT AND THE CONTRACTOR IS RESPONSIBLE FOR COMPLYING WITH ALL EROSION CONTROL MEASURES SHOWN ON THE PLANS. ADDITIONAL EROSION CONTROL MEASURES SHALL BE INSTALLED IF DEEMED
- 7. ALL MATERIAL SCHEDULES SHOWN ON THE PLANS ARE FOR GENERAL INFORMATION ONLY. THE CONTRACTOR SHALL PREPARE HIS OWN MATERIAL SCHEDULES BASED UPON HIS PLAN REVIEW. ALL SCHEDULES SHALL BE VERIFIED IN THE FIELD BY THE CONTRACTOR PRIOR TO ORDERING MATERIALS OR PERFORMING WORK.
- 8. ALL MATERIALS AND CONSTRUCTION METHODS SHALL CONFORM TO THE PROJECT SPECIFICATIONS, THE CITY OF PORTLAND AND SERVICING UTILITY REQUIREMENTS, IN CASES WHERE THESE CONFLICT THE MOST STRINGENT SHALL APPLY AT NO EXTRA COST TO THE OWNER.

NECESSARY BY ONSITE INSPECTIONS OF THE OWNER, THEIR REPRESENTATIVES, OR THE CITY, AT NO ADDITIONAL COST TO THE OWNER.

- 9. THE CONTRACTOR IS RESPONSIBLE FOR MAINTAINING RECORD DRAWINGS THROUGHOUT THE PROJECT AND PROVIDING THE OWNER WITH A SET OF ELECTRONIC FINAL RECORD DRAWINGS WHEN THE PROJECT IS COMPLETE.
- 10. THE CONTRACTOR IS RESPONSIBLE FOR MAINTAINING ACCESS TO THE SITE AND ALL ADJACENT PROPERTIES INCLUDING NGL-NE SITE AND MDOT MAINTENANCE BUILDING AT ALL TIMES. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL TEMPORARY MARKINGS, SIGNAGE AND INCIDENTALS TO MAINTAIN SAFE VEHICLE AND PEDESTRIAN ACCESS THROUGH OUT THE LIFE OF THE PROJECT. THE CONTRACTOR SHALL NOTIFY THE PORTLAND PUBLIC SAFETY DIVISION ROUTINELY REGARDING TEMPORARY IMPACT OR CHANGES TO SITE ACCESS CONDITIONS.
- 11. THE CONTRACTOR IS RESPONSIBLE FOR PERFORMANCE OF WORK IN ACCORDANCE WITH ALL AREMA SAFETY STANDARDS AND SHALL COOPERATE FULLY WITH REPRESENTATIVES OF PAN AM RAILWAYS, MDOT, AND UNITIL AS MAY BE REQUIRED.

PERMITTING NOTES

- 1. THIS PROJECT WILL BE SUBJECT TO THE TERMS AND CONDITIONS OF A MAINE DEP NATURAL RESOURCES PROTECTION ACT PERMIT FOR ACTIVITIES WITHIN 75' OF THE RIVER, WHICH WILL BE MADE A PART OF THE CONTRACT BID DOCUMENTS.
- 2. THIS PROJECT IS SUBJECT TO THE TERMS AND CONDITIONS OF THE SITE PLAN REVIEW PERMIT FROM THE CITY OF PORTLAND WHICH WILL BE MADE A PART OF THE CONTRACT BID DOCUMENTS. THE CONSTRUCTION WILL BE GOVERNED BY THE ZONING ORDINANCES WHICH ARE AVAILABLE FOR VIEWING AT THE OFFICE OF THE ENGINEER OR THE MUNICIPAL OFFICE.
- 3. THE PROJECT IS SUBJECT TO THE TERMS AND CONDITIONS OF THE PORTLAND HARBOR COMMISSION APPROVAL WHICH WILL BE MADE PART OF THE CONTRACT BID DOCUMENTS.
- 4. THE CONTRACTOR SHALL REVIEW THE ABOVE-REFERENCED PERMITS PRIOR TO SUBMITTING A BID FOR THIS PROJECT, AND INCLUDE COSTS AS NECESSARY TO COMPLY WITH THE CONDITIONS OF THESE PERMITS.
- THE PROJECT CONSTRUCTION IS SUBJECT TO ALL REQUIREMENTS OF THE VOLUNTARY RESPONSE ACTION PLAN AS PREPARED BY AMEC ON BEHALF OF UNITIL FOR THE NORTHERN UTILITIES PROPERTIES. CREDERE ASSOCIATES IS RESPONSIBLE FOR ENVIRONMENTAL CONSULTATION FOR NEW YARD, LLC AND WILL BE PREPARING ENVIRONMENTAL REPORTS RELATED TO THE PAN AM PROPERTIES FOLLOWING THE PROPERTY TRANSFER AND APPROVED BY THE MAINE DEP. SEE SEPARATE DOCUMENTS PREPARED BY CREDERE ASSOCIATES WHICH ARE TO BE CONSIDERED PART OF THE CONTRACT DOCUMENTS.

SITE LAYOUT NOTES

- 1. BITUMINOUS CONCRETE CURB, SLIPFORM CONCRETE CURB AND GRANITE CURB SHALL MEET THE REQUIREMENTS OF MDOT 702.001, 703.07 AND 609.04.
- 2. ALL DIMENSIONING, UNLESS NOTED OTHERWISE, IS TO THE FACE OF CURB OR THE FACE OF THE BUILDING.
- 3. EXCEPT WHERE INDICATED OTHERWISE, THE PAVEMENT IS TO BE HEAVY DUTY PAVEMENT
- ALL TRAFFIC CONTROL SIGNS INDICATED ON THE SITE LAYOUT PLAN ARE TO MEET ALL REQUIREMENTS & STANDARDS OF THE MAINE DEPARTMENT OF TRANSPORTATION, AND THE MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES, LATEST EDITIONS AND THE AMERICANS WITH DISABILITIES ACT REQUIREMENTS.

GRADING & DRAINAGE NOTES:

- 1. ALL STORM DRAIN PIPE SHALL BE SMOOTH BORE INTERIOR PROVIDING A MANNINGS ROUGHNESS COEFFICIENT OF N = 0.012 OR LESS.
- 2. AN "AS-BUILT" CERTIFICATION AND PLANS OF THE STORMWATER DRAINAGE SYSTEM IS REQUIRED PRIOR TO THE OWNER ACCEPTING ANY BUILDINGS AND PROPERTY. THE CONTRACTOR IS SPECIFICALLY CAUTIONED THAT ANY DEVIATION FROM THE PLANS MAY DELAY THE ACCEPTANCE OF THE PROJECT, WITH CONTRACTOR RESPONSIBLE FOR ANY ASSOCIATED COSTS.
- 3. A DETAILED O&M MANUAL FOR STORMWATER MANAGEMENT SYSTEMS IS (WILL BE) FILED WITH THE CITY OF PORTLAND DURING THE PERMIT REVIEW PROCESS. A SPECIFIC MANUAL HAS BEEN PREPARED FOR O&M OF THE DRAINAGE SYSTEM.
- 4. SEE EXISTING CONDITIONS FOR BENCHMARK INFORMATION.
- 5. SEE GRADING, DRAINAGE AND EROSION/SEDIMENT CONTROL FOR PROPOSED GRADING AND EROSION CONTROL MEASURES.
- 6. ALL DISTURBED AREAS NOT TO BE PAVED, GRAVELED, SODDED OR OTHERWISE TREATED SHALL RECEIVE 6" LOAM, SEED, FERTILIZER AND MULCH.

7. COMPACTION REQUIREMENTS

LOCATION	MINIMUM COMPACTION
SUBBASE AND BASE GRAVEL BELOW PAVED OR CONCRETE AREAS	95%
SUBGRADE FILL BELOW PAVED AREAS	90%
TRENCH BEDDING MATERIAL AND SAND BLANKET BACKFILL	95%
BELOW LOAM AND SEED AREAS	90%
STRUCTURAL FILL WITHIN PROPOSED BUILDING AREA	95%
SELECT FILL ADJACENT BUILDING FOUNDATIONS, EXTERIOR FOUNDATIONS	95%
AND WITHIN 8 INCHES OF THE SLAB-ON-GRADE	

*ALL PERCENTAGES OF COMPACTION SHALL BE OF THE MAXIMUM DRY DENSITY AT THE OPTIMUM MOISTURE CONTENT AS DETERMINED AND CONTROLLED IN ACCORDANCE WITH ASTM-D-1557.

ACCORDANCE WITH ASTM-D-1557.

8. ADJUST ALL MANHOLES, CATCH BASINS, CURB BOXES, ETC. WITHIN LIMITS OF WORK TO FINISH GRADE.

IS SUBJECT TO THE RECOMMENDATIONS OF THE PROJECT GEOTECHNICAL ENGINEER.

PARKING AND SNOW STORAGE. STATUS: COMPLETED, SEE REVISED PLANS.

- 9. CONTRACTOR SHALL PROVIDE A FINISH PAVEMENT SURFACE FREE OF LOW SPOTS AND PONDING AREAS. CRITICAL AREAS INCLUDE BUILDING ENTRANCE AND EXIT RAMPS ADJACENT TO THE BUILDING AND ALONG NEW CURBED AREAS.
- 10. PROVIDE STABILIZATION OR SEPARATION GEOTEXTILE FABRIC OVER UNSTABLE SOILS AS DIRECTED BY THE OWNER'S REPRESENTATIVE AND IN ACCORDANCE
- WITH THE FINAL GEOTECHNICAL RECOMMENDATIONS.

 11. NATIVE SOILS RANGE FROM GRANULAR TO CLAYEY AND SILTY. CARE MUST BE EXERCISED TO LIMIT DISTURBANCE OF THE BEARING SOILS. THE NATIVE CLAYEY OR SILTY SOILS SHOULD NOT BE PROOF-ROLLED. SHOULD THE SUBGRADE BECOME YIELDING OR DIFFICULT TO WORK, DISTURBED AREAS SHOULD BE EXCAVATED AND BACKFILLED WITH COMPACTED SELECT FILL OR CRUSHED STONE AT NO EXTRA EXPENSE TO THE OWNER. ALL SUBGRADE PREPARATION

LOCAL APPROVALS, WAIVERS AND VARIANCES

THE CONSTRUCTION PLANS ARE TO BE SUBMITTED TO THE CITY OF PORTLAND FOR THEIR REVIEW, APPROVAL AND RECORDS PRIOR TO THE COMMENCEMENT OF CONSTRUCTION.

ORIGINAL SITE PLAN CONDITIONS OF APPROVAL

- 1. MDOT SHARED ENTRANCE: THAT PRIOR TO ISSUANCE OF A BUILDING PERMIT, THE APPLICANT PROVIDES FOR REVIEW AND APPROVAL AN EASEMENT FROM MDOT TO NEW YARD FOR CONSTRUCTION AND USE OF A SHARED ENTRY WAY. STATUS: PENDING DUE TO NEGOTIATIONS FOR IMT EXPANSION.
- BEACH STREET INTERSECTION CONTRIBUTIONS: THAT PRIOR TO ISSUANCE OF A BUILDING PERMIT, THE APPLICANT CONTRIBUTES \$5,000 FOR BEACH STREET INTERSECTION IMPROVEMENTS, INCLUDING BUT NOT LIMITED TO PEDESTRIAN CROSSING AND SIGNALIZATION. STATUS: PENDING.
- 3. COMBINED SEWER OVERFLOW EASEMENT: THAT PRIOR TO ISSUANCE OF A BUILDING PERMIT, THE APPLICANT PROVIDES A 30 FOOT WIDE EASEMENT TO THE CITY FOR THE COMBINED SEWER OVERFLOW LINE CROSSING THE PROPERTY FROM WEST COMMERCIAL STREET TO THE FORE RIVER AS SHOWN ON THE DELUCA-HOFFMAN ASSOCIATES, INC. SITE DEVELOPMENT PLAN, C-2.1, REVISION 4,DATED 12-5-12. STATUS: PENDING.
- 4. OTHER AGENCY REVIEWS: THAT ANY MODIFICATIONS TO CITY APPROVED PLANS TO MEET OUTSIDE AGENCY REQUIREMENTS MUST BE IDENTIFIED AND SUBMITTED TO THE PLANNING AUTHORITY FOR FINAL REVIEW PRIOR TO ISSUANCE OF A BUILDING PERMIT. OUTSIDE AGENCY PERMITS INCLUDE, NRPA WETLAND ALTERNATION PERMITS, MAINE DEP VRAP APPROVALS, AND PORTLAND HARBOR COMMISSION APPROVALS. STATUS: ALL APPROVALS PREVIOUSLY SUBMITTED TO PLANNING AUTHORITY
- 5. RAIL DEMOLITION: THAT PRIOR TO DEMOLITION OF EXISTING RAIL INFRASTRUCTURE, THE APPLICANT EITHER PROVIDES EVIDENCE OF RAIL ABANDONMENT OR A LEGAL OPINION FOR THE REVIEW AND APPROVAL OF CORPORATION COUNSEL THAT SUCH ABANDONMENT IS NOT REQUIRED. STATUS: NO LONGER
- 6. <u>FLOOD PLAIN MANAGEMENT:</u> THAT PRIOR TO ISSUANCE OF A BUILDING PERMIT, THE FINAL SITE PLAN IS REVISED TO INCLUDE A NOTE REQUIRING THAT STRUCTURES ON LOTS IN THE DEVELOPMENT BE CONSTRUCTED IN ACCORDANCE WITH PORTLAND CITY CODE, SECTION 14-450.8, FLOOD PLAIN
- MANAGEMENT. STATUS: COMPLETED, SEE SHEET C-2.1.

 STORMWATER MANAGEMENT: THAT PRIOR TO ISSUANCE OF A BUILDING PERMIT, THE APPLICANT PROVIDES FOR REVIEW AND APPROVAL A REVISED GRADING AND DRAINAGE PLAN AND SUPPORTING MATERIAL CONSISTENT WITH CONSULTING STORMWATER ENGINEER, DAVE SENUS' REVIEW MEMO DATED
- DECEMBER 14, 2012, INCLUDED AS ATTACHMENT 4 OF PLANNING REPORT #53-12. STATUS: COMPLETED.

 8. FIRE SAFETY AND EMERGENCY ACCESS: THAT PRIOR TO ISSUANCE OF A BUILDING PERMIT, THE APPLICANT SUBMIT A REVISED SITE PLAN FOR REVIEW AND APPROVAL IN COMPLIANCE WITH THE DECEMBER 12, 2012 FIRE CODE ANALYSIS MEMO FROM FIRE RISK MANAGEMENT, INC. (ATTACHMENT U OF PLANNING REPORT #53-12). THE REVISED SITE PLAN WILL SHOW EMERGENCY ACCESS ROUTES TO BE KEPT CLEAR OF STORED AND TRAILERED VESSELS, VEHICLE
- 9. <u>UTILITY CAPACITY:</u> THAT PRIOR TO ISSUANCE OF A BUILDING PERMIT, THAT ELECTRICAL, GAS, AND SEWER CAPACITY LETTERS ARE PROVIDED TO THE PLANNING AUTHORITY. STATUS: COMPLETED.

STANDARD CONDITIONS OF APPROVAL

- DEVELOP SITE ACCORDING TO PLAN: THE SITE SHALL BE DEVELOPED AND MAINTAINED AS DEPICTED ON THE SITE PLAN AND IN THE WRITTEN SUBMISSION OF THE APPLICANT. MODIFICATION OF ANY APPROVED SITE PLAN OR ALTERATION OF A PARCEL WHICH WAS THE SUBJECT OF SITE PLAN APPROVAL AFTER MAY 20, 1974, SHALL REQUIRE THE PRIOR APPROVAL OF A REVISED SITE PLAN BY THE PLANNING BOARD OR PLANNING AUTHORITY PURSUANT TO THE TERMS OF CHAPTER 14, LAND USE, OF THE PORTLAND CITY CODE.
- 2. <u>SEPARATE BUILDING PERMITS ARE REQUIRED:</u> THIS APPROVAL DOES NOT CONSTITUTE APPROVAL OF BUILDING PLANS, WHICH MUST BE REVIEWED AND APPROVED BY THE CITY OF PORTLAND'S INSPECTION DIVISION.
- SITE PLAN EXPIRATION: THE SITE PLAN APPROVAL WILL BE DEEMED TO HAVE EXPIRED UNLESS WORK HAS COMMENCED WITHIN ONE (1) YEAR OF THE APPROVAL OR WITHIN A TIME PERIOD UP TO THREE (3) YEARS FROM THE APPROVAL DATE AS AGREED UPON IN WRITING BY THE CITY AND THE APPLICANT. REQUESTS TO EXTEND APPROVALS MUST BE RECEIVED BEFORE THE ONE (1) YEAR EXPIRATION DATE.
- 4. PERFORMANCE GUARANTEE AND INSPECTION FEES: A PERFORMANCE GUARANTEE COVERING THE SITE IMPROVEMENTS, INSPECTION FEE PAYMENT OF 2.0% OF THE GUARANTEE AMOUNT AND SEVEN (7) FINAL SETS OF PLANS MUST BE SUBMITTED TO AND APPROVED BY THE PLANNING DIVISION AND PUBLIC SERVICES DEPARTMENT PRIOR TO THE RELEASE OF A BUILDING PERMIT, STREET OPENING PERMIT OR CERTIFICATE OF OCCUPANCY FOR SITE PLANS. IF YOU NEED TO MAKE ANY MODIFICATIONS TO THE APPROVED PLANS, YOU MUST SUBMIT A REVISED SITE PLAN APPLICATION FOR STAFF REVIEW AND APPROVAL.
- DEFECT GUARANTEE: A DEFECT GUARANTEE, CONSISTING OF 10% OF THE PERFORMANCE GUARANTEE, MUST BE POSTED BEFORE THE PERFORMANCE GUARANTEE WILL BE RELEASED.
- 6. PRECONSTRUCTION MEETING: PRIOR TO THE RELEASE OF A BUILDING PERMIT OR SITE CONSTRUCTION, A PRE-CONSTRUCTION MEETING SHALL BE HELD AT THE PROJECT SITE. THIS MEETING WILL BE HELD WITH THE CONTRACTOR, DEVELOPMENT REVIEW COORDINATOR, PUBLIC SERVICE'S REPRESENTATIVE AND OWNER TO REVIEW THE CONSTRUCTION SCHEDULE AND CRITICAL ASPECTS OF THE SITE WORK. AT THAT TIME, THE DEVELOPMENT REVIEW COORDINATOR WILL CONFIRM THAT THE CONTRACTOR IS WORKING FROM THE APPROVED SITE PLAN. THE SITE/BUILDING CONTRACTOR SHALL PROVIDE THREE (3) COPIES OF A DETAILED CONSTRUCTION SCHEDULE TO THE ATTENDING CITY REPRESENTATIVES. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO ARRANGE A MUTUALLY AGREEABLE TIME FOR THE PRE-CONSTRUCTION MEETING (IF APPLICABLE).
- DEPARTMENT OF PUBLIC SERVICES PERMITS: IF WORK WILL OCCUR WITHIN THE PUBLIC RIGHT-OF-WAY SUCH AS UTILITIES, CURB, SIDEWALK AND DRIVEWAY CONSTRUCTION, A STREET OPENING PERMIT(S) IS REQUIRED FOR YOUR SITE. PLEASE CONTACT CAROL MERRITT AT 874-8300, EXT. 8828. (ONLY EXCAVATORS LICENSED BY THE CITY OF PORTLAND ARE ELIGIBLE.)
- AS-BUILT FINAL PLANS: FINAL SETS OF AS-BUILT PLANS SHALL BE SUBMITTED DIGITALLY TO THE PLANNING DIVISION, ON A CD OR DVD, IN AUTOCAD FORMAT (*,DWG), RELEASE AUTOCAD 2005 OR GREATER.
- 9. STORMWATER MANAGEMENT: THAT THE DEVELOPER/ CONTRACTOR/ SUBCONTRACTOR MUST COMPLY WITH CONDITIONS OF THE CONSTRUCTION STORMWATER MANAGEMENT PLAN AND SEDIMENT & EROSION CONTROL PLAN BASED ON CITY STANDARDS AND STATE GUIDELINES; THAT THE OWNER/OPERATOR OF THE APPROVED STORMWATER MANAGEMENT SYSTEM AND ALL ASSIGNS SHALL COMPLY WITH THE CONDITIONS OF CHAPTER 32 STORMWATER INCLUDING ARTICLE III, POST-CONSTRUCTION STORMWATER MANAGEMENT, WHICH SPECIFIES THE ANNUAL INSPECTIONS AND REPORTING REQUIREMENTS; AND THAT A MAINTENANCE AGREEMENT FOR THE STORMWATER DRAINAGE SYSTEM, AS ATTACHED, OR IN SUBSTANTIALLY THE SAME FORM WITH ANY CHANGES TO BE APPROVED BY CORPORATION COUNSEL, SHALL BE SUBMITTED AND SIGNED PRIOR TO THE ISSUANCE OF A CERTIFICATE OF OCCUPANCY WITH A COPY TO THE DEPARTMENT OF PUBLIC SERVICES.

ORGINAL WAIVERS (SUBJECT TO AMENDED SITE PLAN REVIEW)

- THE PLANNING BOARD FINDS THAT TWO OR MORE CRITERIA FOR SIDEWALK WAIVER, AS PROVIDED UNDER SEC.14 -506 (B), (ARE) MET, NAMELY THAT: A SAFE ALTERNATIVE-WALKING ROUTE IS REASONABLY AVAILABLE BY WAY OF A SIDEWALK ON THE OTHER SIDE OF THE STREET, AND CONSTRUCTION OF THE SIDEWALK WILL RESULT IN LOSS OF SIGNIFICANT FEATURES OF GREATER VALUE (TRUCK CIRCULATION); AND THEREFORE (WAIVES) THE REQUIREMENT FOR SIDEWALKS ALONG THE SOUTHERLY SIDELINE OF WEST COMMERCIAL STREET.
- THE PLANNING BOARD FINDS THAT TWO OR MORE CRITERIA FOR GRANITE CURBING WAIVER, AS PROVIDED UNDER SEC.14 -506 (B), (ARE) MET, NAMELY THAT: CONSTRUCTION OF THE CURBING WILL RESULT IN LOSS OF SIGNIFICANT FEATURES OF GREATER VALUE (TRUCK CIRCULATION); AND THAT CURBING IS NOT NECESSARY FOR STORMWATER MANAGEMENT; AND THEREFORE (WAIVES) THE REQUIREMENT FOR GRANITE CURBING ALONG THE SOUTHERLY SIDELINE OF WEST COMMERCIAL STREET.
- THE PLANNING BOARD **(WAIVES)** THE TECHNICAL STANDARD FOR FLOODING AS PROVIDED TECHNICAL MANUAL III. 4. E.(2) WAIVER OF THE FLOODING STANDARD DUE TO DIRECT DISCHARGE INTO THE OCEAN, A GREAT POND, OR MAJOR RIVER SEGMENT.
- THE PLANNING BOARD **(WAIVES)** THE TECHNICAL STANDARD FOR LANDSCAPING, SEC. IV. 5.4.5, FOR TREE SPECIES AND SIZE TO ALLOW A NATURALIZED REPLANTING PROGRAM CONSISTENT WITH THE SITE'S SHORELAND ZONE CONTEXT.
- THE PLANNING BOARD (WAIVES) THE TECHNICAL STANDARD FOR SITE LIGHTING SEC. XII. 2., ILLUMINATION LEVELS AND UNIFORMITY LEVELS.
- THE PLANNING BOARD (WAIVES) THE TECHNICAL STANDARD FOR SOIL INFILTRATION TESTING, SEC. V, APPENDIX D.4.(A) BASED ON KNOWN CONDITIONS ON THE SITE AND CONTROLLED MATERIALS TO BE INSTALLED WITH CONSTRUCTION.
- 7. THE PLANNING BOARD **(WAIVES)** THE REQUIREMENT FOR BICYCLE PARKING, SITE PLAN STANDARD 14-526 A (4) B., BASED ON AN INDUSTRIAL USE LOCATED IN AN OUTLYING AREA.
- STAFF RECOMMENDS A PARTIAL WAIVER REQUIRING HALF (4) OF THE REQUIRED 8 BICYCLE PARKING SPACES.
- 8. THE PLANNING BOARD (WAIVES) THE TECHNICAL STANDARD FOR DRIVEWAY WIDTH, SEC I.7.1.4., 36 FOOT MAXIMUM WIDTH. 48 FEET IS REQUESTED DUE TO LARGE TRUCK AND TRAILER TURNING MOVEMENTS.

<u>UTILITY NOTES</u>

- 1. ALL REQUIRED UTILITIES SERVING THE PROJECT SHALL BE COORDINATED AND CONSTRUCTED BY THE SITE CONTRACTOR TO WITHIN 5 FEET OF THE BUILDINGS, AT A LOCATION COORDINATED WITH THE MEP CONTRACTOR(S) AND THE BUILDING PLANS. SITE WORK WITHIN 5 FEET OF UNDERSLAB UTILITIES SHALL CONSIST OF TRENCHING AND BACKFILLING. ACTUAL UTILITY INSTALLATION SHALL BE BY THE MEP CONTRACTOR. ALL REQUIRED CONNECTION FEES SHALL BE PAID BY THE GENERAL CONTRACTOR.
- THE CONTRACTOR SHALL COORDINATE THE INSTALLATION OF AND/OR RELOCATION OF OVERHEAD AND UNDERGROUND TELEPHONE WITH FAIRPOINT COMMUNICATIONS. CONTRACTOR SHALL BE RESPONSIBLE FOR CONDUITS, PULL WIRES, TRENCHING AND BACKFILLING NECESSARY TO COMPLETE THE
- 3. ALL SANITARY SEWER WORK SHALL MEET THE STANDARDS OF THE MAINE STATE PLUMBING CODE AND CITY OF PORTLAND PUBLIC SERVICES DIVISION.

 CONNECTIONS TO THE 42" SAN. SEWER AND 24" CSO LINE SHALL BE PERFORMED IN ACCORDANCE WITH CITY OF PORTLAND PUBLIC SERVICES DIVISION RECOMMENDATIONS AND REGULATIONS.
- 4. THE CONTRACTOR SHALL COORDINATE THE INSTALLATION OF ELECTRIC SERVICE WITH CENTRAL MAINE POWER. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL TRENCHING, CONDUIT AND BACKFILLING ASSOCIATED WITH UNDERGROUND POWER, COMMUNICATIONS AND CABLE.
- 5. COORDINATE ALL OTHER UTILITY WORK WITH THE APPROPRIATE UTILITY COMPANY. ALL UTILITY WORK SHALL CONFORM TO THE STANDARDS OF THE UTILITY COMPANY AND PROJECT SPECIFICATIONS, WHICHEVER IS MORE STRINGENT, AT NO EXTRA EXPENSE TO THE OWNER.
- 6. THE LOCATIONS OF THE NEW UTILITY SERVICES AND CONNECTIONS SHALL BE COORDINATED WITH THE SERVING UTILITY COMPANY, PROJECT ARCHITECTS AND MEP DESIGNERS.
- UNDERGROUND ELECTRICAL, CONDUIT MATERIAL AND INSTALLATION SHALL CONFORM TO CENTRAL MAINE POWER STANDARDS AND PROJECT
- SPECIFICATIONS, WHICH EVER IS MORE STRINGENT. THE EXISTING 115KV TRANSMISSION LINE SHALL BE MARKED/FLAGGED AND PROTECTED DURING CONSTRUCTION. WORK ADJACENT TO THE UNE SHALL BE MONITORED BY CENTRAL MAINE POWER.
- 8. ADJUST ALL MANHOLES, CATCH BASINS, CURB BOXES, ETC. WITHIN LIMITS OR WORK TO FINISH GRADE.
- 9. ALL UNDERGROUND CONDUITS SHALL HAVE NYLON PULL ROPES TO FACILITATE PULLING CABLES.
 10. THE CONTRACTOR SHALL OBTAIN, PAY FOR, AND COMPLY WITH ALL REQUIRED PERMITS, ARRANGE FOR ALL INSPECTIONS, AND SUBMIT COPIES OF
- ACCEPTANCE CERTIFICATES TO THE OWNER PRIOR TO COMPLETION OF THE PROJECT.

 11. THE CONTRACTOR SHALL PROVIDE AND INSTALL ALL BOXES, FITTINGS, CONNECTORS, COVER PLATES AND OTHER MISCELLANEOUS ITEMS NOT NECESSARILY
- DETAILED ON THE DRAWINGS TO RENDER INSTALLATION OF UTILITIES COMPLETE AND OPERATIONAL, AT NO EXTRA EXPENSE TO THE OWNER.
- 12. A 10 FOOT MINIMUM EDGE TO EDGE HORIZONTAL SEPARATION SHALL BE PROVIDED BETWEEN ALL WATER AND SANITARY SEWER LINES. AN 18 INCH OUTSIDE TO OUTSIDE VERTICAL SEPARATION SHALL BE PROVIDED AT ALL WATER AND SANITARY SEWER CROSSINGS.
- 13. THE CONTRACTOR SHALL PHASE UTILITY CONSTRUCTION AND PROVIDE TEMPORARY SERVICES AS REQUIRED TO PROVIDE CONTINUOUS SERVICE TO THE JOB SITE. TEMPORARY SERVICES SHALL COMPLY WITH ALL FEDERAL, STATE, LOCAL AND UTILITY COMPANY STANDARDS. COORDINATE ALL TEMPORARY SERVICES WITH UTILITY COMPANY, OWNER AND AFFECTED BUSINESSES.
- 14. REMOVAL AND RELOCATION OF THE EXISTING GAS RELATED FACILITIES SHALL BE COORDINATED WITH UNITIL AND THEIR ASSIGNS. CONTRACTOR TO COORDINATE WITH UNITIL'S CONTRACTOR FOR RELOCATION OF THE 8" GAS LINE AND INSTALLATION OF VAULT (SEE UTILITY PLAN FOR LOCATION).

EROSION CONTROL NOTES:

BASIS, BUT AT A MINIMUM ONCE A WEEK.

- PRIOR TO BEGINNING ANY LAND DISTURBING ACTIVITIES, CLEARING AND GRADING LIMITS SHALL BE STAKED BY THE CONTRACTOR BASED ON THE LIMITS OF GRADING SHOWN ON THE DRAWINGS AND ACCEPTED BY THE OWNER'S REPRESENTATIVE IN THE FIELD. AFTER THE CLEARING AND GRADING LIMITS HAVE BEEN ACCEPTED, THE CONTRACTOR SHALL INSTALL THE PERIMETER SILT FENCES, SEDIMENT BARRIERS AND THE CONSTRUCTION ENTRANCES ASSOCIATED
- ALL GROUND AREAS GRADED FOR CONSTRUCTION SHALL BE GRADED, LOAMED, SEEDED AND MULCHED AS SOON AS POSSIBLE. TEMPORARY/PERMANENT
- SEED MIXTURES SHALL CONFORM TO THE SEEDING PLAN CONTAINED IN THE EROSION CONTROL PROJECT PREPARED FOR THIS PROJECT.


 3. PRIOR TO PAVING OR GRAVEL PLACEMENT, THE CONTRACTOR SHALL REMOVE SILL FROM ALL STORM LINES AND APPLIEDANCES.
- PRIOR TO PAVING OR GRAVEL PLACEMENT, THE CONTRACTOR SHALL REMOVE SILT FROM ALL STORM LINES AND APPURTANCES.
 ALL STORM DRAIN INLETS AND OUTLETS NOT IN PAVED AREAS ARE TO RECEIVE RIPRAP PROTECTION APRONS DURING CONSTRUCTION.
- 5. SILT BARIRIERS SHALL BE INSPECTED, REPAIRED AND CLEANED AS NOTED IN THE EROSION CONTROL NOTES SHOWN ON THE EROSION CONTROL DETAIL
- 6. THE CONTRACTOR SHALL REPAIR AND ADD STONE TO THE CONSTRUCTION ENTRANCES AS IT BECOMES SATURATED WITH MUD TO ENSURE THAT IT FUNCTIONS TO CAPTURE MUD FROM THE TIRES OF CONSTRUCTION VEHICLES DURING CONSTRUCTION. THE PURPOSE OF THE CONSTRUCTION ENTRANCE IS TO KEEP ADJACENT STREETS CLEAR OF DIRT AND MUD. SWEEPING OF THE ROADWAYS SHALL BE PERFORMED BY THE CONTRACTOR ON AN AS NEEDED
- 7. SILT REMOVED FROM AROUND INLETS AND BEHIND THE SILT FENCES SHALL BE PLACED ON A TOPSOIL STOCKPILE AND MIXED INTO TOPSOIL FOR USE IN
- 8. LAND DISTURBING ACTIVITIES SHALL BE ACCOMPLISHED IN A MANNER AND SEQUENCE WHICH CAUSE THE LEAST PRACTICAL UNPROTECTED DENUDED AREAS ON THE SITE DURING CONSTRUCTION.
- 9. THE CONTRACTOR IS CAUTIONED THAT FAILURE TO COMPLY WITH THE SEQUENCE OF CONSTRUCTION, EROSION/SEDIMENT CONTROL PLAN, AND OTHER PERMIT REQUIREMENTS MAY RESULT IN MONETARY PENALTIES AS ENFORCED BY THE MEDEP OR LOCAL AGENCIES. THE CONTRACTOR SHALL BE ASSESSED ALL SUCH PENALTIES AT NO COST TO THE OWNER OR PERMITTEE.
- 1. PROVIDE INLET PROTECTION BARRIERS AROUND ALL EXISTING AND PROPOSED STORM DRAINAGE INLETS AS SHOWN AND MAINTAIN FOR THE DURATION OF THE PROJECT UNTIL PAVEMENT HAS BEEN INSTALLED.

10. A FULL EROSION/SEDIMENTATION CONTROL PLAN ACCOMPANIES THIS DRAWING SET AND IS ALSO CONTAINED IN THE DIV 312513 SPECIFICATIONS.

- 12. INSPECT EROSION AND SEDIMENT CONTROL DEVICES AFTER EACH RAIN STORM OF 0.25 INCHES OR GREATER. REPAIR/MODIFY PROTECTION AS NECESSARY
- TO MAXIMIZE FILTER EFFICIENCY. REPLACE ALL FILTERS WHEN SEDIMENT IS 1/3 OF THE STRUCTURE HEIGHT.

 13. INSTALL CURLEX EROSION CONTROL MAT OR EQUAL ON ALL SLOPES STEEPER THAN 4:1. TURF REINFORCEMENT (NORTH AMERICAN GREEN OR EQUL) SHALL BE USED ON SLOPES STEPPER THAN 3:1 IF NOT CALLED OUT FOR RIPRAP STABILIZATION.
- 14. THE CONTRACTOR SHALL INSTALL ALL EROSION CONTROL MEASURES IN ACCORDANCE WITH THE "MAINE EROSION AND SEDIMENT CONTROL HANDBOOK FOR CONSTRUCTION: BEST MANAGEMENT PRACTICES, CUMBERLAND COUNTY SOIL AND WATER CONSERVATION DISTRICT AND MAINE DEPARTMENT OF ENVIRONMENTAL PROTECTION, MARCH 2003".

LEGEND



ZONING INFORMATION

ZONE: WATERFRONT PORT DEVELOPMENT ZONE (WPDZ) PERMITTED USES: MARINE REPAIR SERVICES / BOAT REPAIR YARD PROVIDED MINIMUM LOT SIZE 22.0 AC MINIMUM LOT FRONTAGE NONE ±1525 FT MINIMUM YARD DIMENSIONS ±4578 FT NONE ±150 FT NONE SETBACK FROM PIER LINE >100 FT MAXIMUM LOT COVERAGE <45 FT AND MAXIMUM BUILDING HEIGHT 45 FT AND 65 FT ABOVE MEAN SEA <65 FT ABOVE LEVEL MSL

PRELIMINARY - NOT FOR CONSTRUCTION

		TE OF MANY
09.20.13	REVISED PHASE 1B BUILDING ALIGNMENT & RESUBMITTED TO CITY	STEPHENR.
09.03.13	REVISED FOR PHASE 1A & 1B	I DUNNE
02.01.13	RELEASED FOR BIDDING	10 /CENSED IS
10.31.12	FINAL SITE PLAN APPLICATION SUBMISSION	SONAL ENGLIS
08.21.12	PRELIMINARY APPLICATION TO CITY OF PORTLAND	
DATE	DESCRIPTION	P.E. STEPHEN BUSHE
	LIC. # 7429	

CANAL LANDING
AMENDED SITE PLAN

EET TITLE
GENERAL NOTES

AND LEGEND

FAY, SPOFFORD & THORNDIKE, INC ENGINEERS · PLANNERS · SCIENTISTS
778 MAIN ST, SUITE 8, SOUTH PORTLAND, ME 04106

DRAWN: CMW DATE: AUGUST 2013
DESIGNED: SRB SCALE: AS NOTED

C-1.1

FILE NAME: 3091.02-GENERAL NOTES

JOB NO. 3091.02 / SP-M040B

CHECKED: SRB

NEW YARD LLC
58 FORE STREET
PORTLAND, ME 04101