

G.M.Libby and Sons Masonry Inc.

1236 North Road
North Yarmouth, ME 04097
207-671-0487
georgejr@gmlibbyandsons.com

Invoice

DATE	Number
2/7/2018	2485

Customer billing
Alec Jaegerman 398 Spring St. Portland , me.

Project
Chimney top repair

DESCRIPTION	AMOUNT
Item#1: Staging : Stage existing chimney in order to pull apart street side left and backside then rebuild to existing design . Staging labor : three days total set up and breakdown ; \$2770.00 Equipment and staging : \$775.00 Item#1 total : \$3545.00	1,169.85
Item#2: Selectively take apart 20sq/ft of chimney including left ear and rebuild . This is estimated as street face top left (4 sq/ ft) , left face (8 sq/ft) and rear left (8 sq/ft) . We intend to tooth out existing solid brickwork and match to. Existing original chimney bricks will be cleaned for reuse and repair to be assembled with a Type N mortar dyed to match existing . Any new bricks needed are to be restoration waterstruct to match and placed on the rear of chimney as not to change front view from the street. Chimney flashing appears to not be needing any repair/ replacement and will be left in tact. Labor: 5 days with a two man crew , Mason and Laborer: \$3750.00 Materials: \$375.00 Item#2 total ; \$4125.00	1,361.25
Total	\$2,531.10