

Dave Thibeau

From: Dave Thibeau [dthibeau@marvinportland.com]
Sent: Thursday, April 03, 2014 3:01 PM
To: '49foley.m@gmail.com'
Subject: Tilt-Pacs
Attachments: Foley - TP.pdf

14 Orchard St. - Window Replacement
A-11 - Window Details - Wood

Hello again Mark,

Attached is the revised proposal for 14 Orchard St. I have also included some of the specs/details for the tilt-pac product. Please review & let me know if there are any other questions or concerns. Thanks again and best regards.

Here are some specs for the tilt-pacs.

Wood Tilt Pacs

Unit Features

Wood Tilt Pac: WTP

Wood Magnum Tilt Pac: WMTP

Sash:

- Double Hung Tilt Pac
 - Sash thickness: 1 5/16" (33)
 - Top rail width: 2 15/32" (63)
 - Bottom rail width: 3 3/4" (95)
 - Stile width: 1 25/32" (45) → - 3/8" overall

This is just standard dimensions for the stiles & rails. We will have Marvin reduce the stiles (vertical sash rails) by 3/16" and the height of the bottom rail will be reduced by 1". Here is what the "putty" glaze looks like: