

## **Family Crisis Services**

**14 Orchard Street**

### **Project Description**

We propose to remove 39 pair of badly deteriorated and worn wooden sash.

We will replace these with 16 Marvin Tilt-In wooden replacement window kits and 23 vinyl replacement windows.

In all cases the original exterior window trim, sills, and headers will all remain unchanged.

On the interior, the original window band will be reinstalled after the replacement windows have been installed.

There will be no change of architectural features or building materials.

The divided light design of each window will remain the same.

The vinyl replacement windows shall be installed on the side of the building invisible from the street.

The vinyl replacement windows shall be installed behind existing storm windows.