# Sequence of Operations

Reviewed for Code Compliance
Inspections Division
Approved with Conditions
Date: 06/08/17

| | Audio/visual activation | Activate audible/visual signal at FACP & Annunciator | Device Description at FACP & Annunciator | Shutdown of HVAC equipment | Log event in system history | Activate Elevator Fire Hat | Activate Elevator primary or secondary control | Activate Elevator shunt trip | Silence of audible devices Including FACP & annunciator | Release door holders | Release locked doors | Event acknowledgement | Reset of all system functions and all visual devices | Remote transmission to Central Station A=alarm; T=trouble; S=Supervisory; L = log only | Remote indicator |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Manual Pull Stations | X | X | X | | X | | | | | | | | | A | |
| Smoke Detectors | X | X | X | | X | | | | | | | | | A | |
| Heat Detectors | X | X | X | | X | | | | | | | | | A | |
| Water Flow Monitor | X | X | X | | X | | | | | | | | | S | |
| Duct Smokes | | X | X | X | X | | | | | | | | | A | |
| Tamper Switch | | X | X | | X | | | | | | | | | T | |
| Hood Surpression | X | X | X | | X | | | | | | | | | A | |
| FACP/annunciator silence button | | X | X | | X | | | | X | | | | | L | |
| FACP/annunciator acknowledge button | | X | X | | X | | | | | | | X | | | |
| FACP/annunciator reset button | | X | X | | X | | | | | | | | X | L | |
| Removal of any device | | X | X | | X | | | | | | | | | T | |
| Ground fault | | X | X | | X | | | | | | | | | T | |
| System wiring "open" | | X | X | | X | | | | | | | | | T | |
| AC Power loss | | X | X | | X | | | | | | | | | T | |
| Secondary power loss | | X | X | | X | | | | | | | | | T | |
| Telephone line loss | | X | X | | X | | | | | | | | | T | |