

MULEHIDE:

FR DECK PANEL 'C' ROOF DIAPHRAGM SHALL BE BLOCKED WITH 2XSPF#2 NOM. LUMBER FOR A DISTANCE OF 4-0" FROM EACH ENDWALL. FASTENED TO TRUSSES W/ 8D SINKER NAILS @ 6" O.C. ON EDGES & 6" O.C. IN THE FIELD.


ROOF SHEATHING DETAIL

APPROVED TRUSS DESIGN: UNIVERSAL TRUSS MANUFACTURER: P1648701 TRUSS DRAWING. #



GENERAL CROSS-SECTION NOTES:

- UNLESS OTHERWISE SPECIFIED, ALL STEEL MUST COMPLY W/ ASTM A36, YIELD STRENGTH = 36 KSI.
- 2. ALL LAG SCREWS MUST COMPLY W/ ANSI/ ASME B18.2.1 F_{YB} = 60 KSI MINIMUM.
- 3. SEE FOUNDATION PLAN FOR PIER AND TIE-DOWN STRAPPING LOCATIONS, ORIENTATIONS, AND SPECIFICATIONS.



INTERIOR FINISH MATERIAL:

CEILING 1/2" GYP BOARD INSTALLED PER MANUFACTURER'S SPECIFICATIONS (SEASPRAY FINISH)

5/8" TYPE 'X'. GYP. BOARD (VCG THROUGHOUT) INSTALLED PER MANUFACTURERS SPECIFICATIONS WALL

FLOOR - AS NOTED ON PLAN


INTERIOR WALL AND CEILING FINISH SHALL BE CLASS B OR BETTER IN N CORRIDORS AND CLASS C OR BETTER IN ROOMS AND ENCLOSED SPACES.


FLOOR FINISHES SHALL BE CLASS II OR BETTER.

EXTERIOR FINISH MATERIAL:

MULE-HIDE 45 MIL (BLACK) EPDM FULLY ADHERED IN ACCORDANCE WITH ESR-1776 OVER 7/16" MULE-HIDE FR DECK PANEL 'C' INSTALLED PER MANUFACTURERS

WALL - 7/16" SMART PANEL SIDING OVER APPROVED MOISTURE BARRIER INSTALLED PER MANUFACTURERS SPECIFICATIONS.





FIRST STRING SPACE 892 RAILROAD AVE. EAST PEARSON, GEORGIA 31642 (912) 422-6455 DATE: 4-29-17 SCALE : NO SCALE SEE NOTES CODES: REVISIONS: STATES: MAINE A.L.K. FSS5542 SHEET 12 x 56 EDUCATION 4 OF 4 DESTINATION: CROSS SECTION PORTLAND