2464 O/A MODULAR CLASSROOM

23'-7" x 60'-0" ACTUAL SIZE

MAINE DESIGN CODES

2009 INTERNATIONAL BUILDING CODE
2009 INTERNATIONAL MECHANICAL CODE
2007 ANSI / ASHRAE 62.1
2009 MAINE STATE INTERNAL PLUMBING CODE
2011 NATIONAL ELECTRIC CODE

DESIGN LIVE LOADS

FLOOR:	40 PSF LIVE LOAD 10 PSF DEAD LOAD
ROOF:	60 PSF GROUND SNOW LOAD 10 PSF DEAD LOAD
CONSTRUCTION TYPE:	5B- UNPROTECTED
OCCUPANCY/USE GROUP:	B
BUILDING AREA:	1,410 SQ FT.
MINIMUM BUILDING SET BACK:	GREATER THAN 10 FEET TO A COMMON OR ASSUMED PROPERTY LINE
SEISMIC ZONE:	GROUP I, CATEGORY C
MAXIMUM WIND LOAD:	120 MPH ULTIMATE WIND SPEED. CATEGORY II, EXPOSURE C
OCCUPANT LOAD:	42 (BASED ON THE HVAC SYSTEM DESIGN)

DRAWING INDEX

DRAWING NUMBER	DESCRIPTION
#1	SPECIFICATIONS
#2	ELEVATIONS
#3	FLOOR PLAN
#4	ELECTRICAL PLAN
#5	HVAC LAYOUT
#6	CROSS SECTION
#7	PLUMBING SCHEMATICS
#8	FOUNDATION PLAN

STATE OF MAINE
Pin-Shi Peter Lee
12156
LICENSED
PROFESSIONAL ENGINEER
APR 28 2017

SERIAL NUMBERS:
CPX-95634 A & B
CPX-95635 A & B
CPX-95636 A & B

SITE LOCATION:
WAYNFLETE SCHOOL
360 SPRING STREET
PORTLAND, MAINE 04102

CITY OF PORTLAND, MAINE RESURGAM
Reviewed for Code Compliance
Inspections Division
Approved with Conditions
Date: 06/20/17

JOB NO: 21
DRAWING NO
DATE: 4/12/17
SCALE: nts

WILLIAMS SCOTSMAN, INC.
325 RODMAN ROAD, AUBURN, ME 04210

DRAWN BY: R.M.
REV:

TITLE: COVER SHEET
MODEL: 2464 O/A CLASSROOM