



Marvin Design Gallery by Eldredge
317 Marginal Way
Portland, Maine 041010
(207) 772-2003 Fax: (207) 772-0418
Sales Person: Jeremy Bate, CDT
jbate@marvinportland.com
www.marvinbyeldredge.com

January 15, 2015

McCargo, Heather
320 Spring St
Portland, ME
Home: (207) 326-8697
Mobile: (207) 266-3916
Email: hmccargo@wildblue.net

Project: 320 Spring St- McCargo/McNiff House

PROPOSAL

BUDGET PRICING-SITE VISIT REQUIRE TO DETERMINE MATERIALS AND PROPER SIZING PRIOR TO ORDER

Marvin Design Gallery by Eldredge proposes to furnish all labor and material necessary for the improvements located at the customer's address according to the following specifications:

Scope of Work to be Performed

Budget to replace total of 8 windows in basement masonry openings.

Table with 3 columns: Item#, Location, and Unit Price. Item 1: Basement Tilt Turn, Qty: 2, Unit Price: \$1,337.40, Total: \$2,674.80. Description includes manufacturer details, glass type, and materials.

Item#: 2 Location: Integrity Awning Qty: 2 Unit Price: \$607.16 Total: \$1,214.32



Manufacturer: Marvin; product line: Integrity awning – roto operating; surface: wood/fiberglass; call number: custom; rough opening: 37" x 31 1/4"; 6 9/16" jamb depth; insulated glass – 1 lite; LOE 180 with argon; 7/8" rectangular simulated divided lite – with spacer bar – special lite cut 3 wide x 1 high: ebony exterior – white interior; white folding handle; white interior; wood interior – ultrex exterior; ebony exterior; screen: interior aluminum screen: screen wire: charcoal fiberglass mesh, screen: white frame; nailing fin.

***Note: Divided lite cut alignment may not be accurately represented in the OMS drawing. Please consult your local representative for exact specifications.

Item#: 3 Location: Integrity Awning Qty: 4 Unit Price: \$532.34 Total: \$2,129.36



Manufacturer: Marvin; product line: Integrity awning – roto operating; surface: wood/fiberglass; call number: custom; rough opening: 37" x 20 1/2"; 6 9/16" jamb depth; insulated glass – 1 lite; LOE 180 with argon; 7/8" rectangular simulated divided lite – with spacer bar – special lite cut 3 wide x 1 high: ebony exterior – white interior; white folding handle; white; wood interior – ultrex exterior; ebony exterior; screen: screen: interior aluminum screen: screen wire: charcoal fiberglass mesh, screen: white frame; nailing fin.

***Note: Divided lite cut alignment may not be accurately represented in the OMS drawing. Please consult your local representative for exact specifications.

<u>Total Material</u>	\$6,018.48
Sub Total	\$6,018.48
Sales Tax (5.5%)	\$331.02
<u>Total Labor Cost</u>	\$3,200.00

Total Installation, Material And Tax As Specified Above: \$9,549.50

Payment schedule terms

- \$4,274.75** upon acceptance
- \$4,274.75** before delivery of product and start of installaion
- \$1,000.00** upon completion

THIS PROPOSAL IS VALID Until January 27th, 2015

Acceptance Of Proposal

Acceptance of Budget to proceed with final measurements and order.

Accepted: _____
McCargo, Heather or McNiff, Brian Date
