

DISPLAY THIS CARD ON PRINCIPAL FRONTAGE OF WORK



CITY OF PORTLAND BUILDING PERMIT

This is to certify that

MCFARLANE WILLIAM & CONSTANCE
BLOOMFIELD JTS

Located at

380 DANFORTH ST

PERMIT ID: 2017-01569

ISSUE DATE: 10/20/2017

CBL: 061 I003001

has permission to **Install NFPA 13D sprinkler system in two family home.**

provided that the person or persons, firm or corporation accepting this permit shall comply with all of the provisions of the Statutes of Maine and of the Ordinances of the City of Portland regulating the construction, maintenance and use of the buildings and structures, and of the application on file in the department.

Notification of inspection and written permission procured before this building or part thereof is lathed or otherwise closed-in. 48 hour notice is required.	A final inspection must be completed before this building or part thereof is occupied. If a certificate of occupancy is required, it must be procured prior to occupancy.
---	---

/s/ David Petruccelli

/s/ Michael Russell, MS, Director

Fire Official

Building Official

**THIS CARD MUST BE POSTED ON THE STREET SIDE OF THE PROPERTY
THERE IS A PENALTY FOR REMOVING THIS CARD**

Approved Property Use - Zoning

Building Inspections

Fire Department

BUILDING PERMIT INSPECTION PROCEDURES
Please call 874-8703
or email: buildinginspections@portlandmaine.gov

**Check the Status of Permit or Schedule an Inspection at
<http://www.portlandmaine.gov/planning/permitstatus.asp>**

With the issuance of this permit, the owner, builder or their designee is required to provide adequate notice to the City of Portland Inspections Division for the inspections listed below. Appointments must be requested 48 to 72 hours in advance. The inspection date will need to be confirmed by this office.

- **Please read the conditions of approval that are attached to this permit.**
- **Permits expire in 6 months if the project is not started or ceases for 6 months.**
- **If the inspection requirements below are not followed, then additional fees may be incurred due to the issuance of a "Stop Work Order" and subsequent release to continue.**
- **Per Section 107.3.1 of the Maine Uniform Building and Energy Code (MUBEC), one set of printed approved stamped construction documents will be kept at the site of work and open to inspection by building officials.**

REQUIRED INSPECTIONS:

Final - Fire

The project cannot move to the next phase prior to the required inspection and approval to continue.

If the permit requires a certificate of occupancy, it must be paid and issued to the owner or designee before the space may be occupied.

City of Portland, Maine - Building or Use Permit		Permit No: 2017-01569	Date Applied For: 10/05/2017	CBL: 061 I003001
389 Congress Street, 04101 Tel: (207) 874-8703, Fax: (207) 874-8716				
Proposed Use: Same. Two residential condominiums.		Proposed Project Description: Install NFPA 13D sprinkler system in two family home.		
Dept: Historic		Status: Approved w/Conditions	Reviewer: Robert Wiener	Approval Date: 10/20/2017
Note:		Ok to Issue: <input checked="" type="checkbox"/>		
Conditions:		1) Should any exterior equipment be required, the location is to be reviewed and approved by HP staff prior to installation. Call 756-8023.		
Dept: Fire		Status: Approved w/Conditions	Reviewer: David Petrucci	Approval Date: 10/10/2017
Note:		Ok to Issue: <input checked="" type="checkbox"/>		
Conditions:		1) NFPA 1 Fire Code Per 1.14.4 Review and approval by the AHJ shall not relieve the applicant of the responsibility of compliance with this Code.		
		2) A copy of the required state sprinkler permit with RMS signoff shall be provided prior to the final inspection.		
		3) A warning sign, with minimum ¼ in. letters, shall be affixed adjacent to the main shutoff valve and shall state the following: Warning: The water system for this house supplies fire sprinklers that require certain flows and pressures to fight a fire. Devices that restrict the flow or decrease the pressure or automatically shut off the water to the fire sprinkler system, such as water softeners, filtrations systems, and automatic shut off valves, shall not be added to this system without a review of the fire sprinkler system by a fire protection specialist. Do not remove this sign.		
		4) All control valves shall be supervised in accordance with NFPA 13D. Pad locks shall only be installed on valves designed to be secured in the open position by pad lock.		
		5) The sprinkler system shall be installed in accordance with NFPA 13D.		