

DOOR SCHEDULE

Door No.	Location	Style	Door Width	Height	Material	Thickness	Type	Frame Material	Head	Jamb	Type	Hdwr. Set See Spec.	Fire Label	Remarks
GROUND FLOOR														
G01	G03 STORAGE	PAIRED FLUSH WOOD	6'-0"	8'-0"	SC WD	1 3/4"	D3	HM	SIM. J9	J9	F1	HW 12		
G02	G03 STORAGE (EXT)	PAIRED FLUSH METAL	6'-0"	7'-0"	HM-INSUL	1 3/4"	D1	HM	H2	J13	F1	HW 18		W/ WOOD TRIM
G03	G04 DANCE STORAGE	FLUSH WOOD	3'-0"	7'-4"	SC WD	1 3/4"	D4	HM	SIM. J1	J1	F2	HW 8		
G04	G02 ELEC. CLOSET	FLUSH WOOD	3'-0"	7'-0"	SC WD	1 3/4"	D3	HM	SIM. J3	J3	F1	HW 20		PROVIDE PANIC HARDWARE
G05	G01E CLOSET	FLUSH WOOD	3'-0"	7'-0"	SC WD	1 3/4"	D4	HM	SIM. J7	SIM. J7	F2	HW 8		
G06	G01D CLOSET	FLUSH WOOD	3'-0"	7'-0"	SC WD	1 3/4"	D4	HM	SIM. J7	SIM. J7	F2	HW 8		
G07	G01C CLOSET	FLUSH WOOD	3'-0"	7'-0"	SC WD	1 3/4"	D4	HM	SIM. J7	SIM. J7	F2	HW 8		
G08	G01B CLOSET	FLUSH WOOD	3'-0"	7'-0"	SC WD	1 3/4"	D4	HM	SIM. J7	SIM. J7	F2	HW 8		
G09	G01A CLOSET	FLUSH WOOD	3'-0"	7'-0"	SC WD	1 3/4"	D4	HM	SIM. J7	SIM. J7	F2	HW 8		
G10	STAIR ONE	FLUSH WOOD	3'-0"	7'-0"	SC WD	1 3/4"	D6	HM	SIM. J2	J2	F2	HW 5		1 HR RATED
G11	STAIR ONE (EXT)	FLUSH WOOD	3'-0"	7'-0"	SC WD-INSUL	1 3/4"	D8	HM	H2	J13	F3	HW 2		
G12	109 THEATER	PAIRED FLUSH WOOD	6'-0"	8'-0"	SC WD	1 3/4"	D1	HM	SIM. J9	J9	F1	HW 6		W/ INT. WOOD TRIM: SIM TO DOOR G16
G13	G14 EAST WING	PAIRED FLUSH WOOD	6'-0"	8'-0"	SC WD	1 3/4"	D1	HM	SIM. J9	J9	F1	HW 13		W/ SOUND GASKETING
G14	G12 WEST WING	PAIRED FLUSH WOOD	6'-0"	8'-0"	SC WD	1 3/4"	D1	HM	SIM. J4	J4	F1	HW 13		W/ SOUND GASKETING/ALUM. THRESHLD
G15	G12 WEST WING	PAIRED FLUSH WOOD	6'-0"	8'-0"	SC WD	1 3/4"	D3	HM	SIM. J4	J4	F1	HW 13		W/ SOUND GASKETING
G16	109 THEATER (EXT)	PAIRED FLUSH METAL	6'-0"	7'-2"	HM-INSUL	1 3/4"	D1	HM	H2	J13	F1	HW 19		W/ WOOD TRIM/BRONZE THRESHOLD
G17	G06 RECYCLING	FLUSH WOOD	3'-0"	7'-0"	SC WD	1 3/4"	D4	HM	SIM. J2	J2	F2	HW 8		
G18	G06 RECYCLING (EXT)	PAIRED FLUSH METAL	6'-0"	8'-0"	HM-INSUL	1 3/4"	D1	HM	H2	J13	F1	HW 17		
G19	G08 DRAMA ROOM	FLUSH WOOD	3'-0"	8'-0"	SC WD	1 3/4"	D6	HM	SIM. J10	J10	F1	HW 10		W/ SOUND GASKETING
G20	G08 DRAMA ROOM	FLUSH WOOD	3'-0"	8'-0"	SC WD	1 3/4"	D6	HM	SIM. J10	J10	F1	HW 9		W/ SOUND GASKETING/ALUM. THRESHLD
G21	G09 ENTRY HALL (EXT)	PAIRED FLUSH METAL	6'-0"	8'-0"	HM-INSUL	1 3/4"	D1	HM	H2	J13	F1	HW 18		
G22	G10 W/C	FLUSH WOOD	3'-0"	7'-0"	SC WD	1 3/4"	D4	HM	SIM. J6	J6	F2	HW 3		SEE PARTITION SCHED. FOR INSUL. INFO
G23	G11 WORKSHOP	FLUSH WOOD	3'-0"	7'-0"	SC WD	1 3/4"	D4	HM	SIM. J6	J6	F2	HW 8		ALUMINUM THRESHOLD
G24	G07 OFFICE	FLUSH WOOD	3'-0"	7'-0"	SC WD	1 3/4"	D6	HM	SIM. J10	J10	F1	HW 9		W/ SOUND GASKETING
G25	G01F INSTRUMENT CLO.	FLUSH WOOD	5'-0"	7'-0"	SC WD	1 3/4"	D3	HM	SIM. J9	J9	F1	HW 14		
G26	G01G INSTRUMENT CLO.	FLUSH WOOD	5'-0"	7'-0"	SC WD	1 3/4"	D2	HM	SIM. J9	J9	F1	HW 14		
FIRST FLOOR														
106	101 LOBBY	PAIRED FLUSH WOOD	6'-0"	7'-0"	SC WD	1 3/4"	D3	HM	SIM. J7	SIM. J7	F1	HW 14		SLIP FRAME W/ WOOD TRIM
107	105 WOMENS RM	FLUSH WOOD	3'-0"	7'-0"	SC WD	1 3/4"	D4	HM	SIM. J6	J6	F2	HW 4		
108	106 MENS RM	FLUSH WOOD	3'-0"	7'-0"	SC WD	1 3/4"	D4	HM	SIM. J6	J6	F2	HW 4		
109	103 JANS CLOSET	FLUSH WOOD	3'-0"	7'-0"	SC WD	1 3/4"	D4	HM	SIM. J3	J3	F2	HW 11		
110	107 THEATER VEST.	PAIRED FLUSH WOOD	6'-0"	7'-0"	SC WD	1 3/4"	D3	WD	SIM. J7	J7	F1	HW 7		W/ SOUND GASKETING
111	107 THEATER VEST.	PAIRED FLUSH WOOD	6'-0"	7'-0"	SC WD	1 3/4"	D3	WD	SIM. J7	J7	F1	HW 1		W/ SOUND GASKETING
112	OMIT													
113	112 EAST FLY	FLUSH WOOD	3'-0"	7'-0"	SC WD	1 3/4"	D4	HM	SIM. J7	SIM. J7	F2	HW 16		SLIP FRAME W/ WOOD TRIM
114	STAIR ONE	FLUSH WOOD	3'-0"	7'-0"	SC WD	1 3/4"	D4	HM	SIM. J7	SIM. J7	F2	HW 1		1 HR RATED
115	114 MUSIC VEST.	PAIRED FLUSH WOOD	6'-0"	7'-0"	SC WD/GLASS	1 3/4"	D7	HM	SIM. J7	SIM. J7	F1	HW 5		SLIP FRAME W/ SOUND GASKETING
116	115 REHEARSAL	FLUSH WOOD	3'-0"	7'-0"	SC WD	1 3/4"	D4	HM	SIM. J7	SIM. J7	F2	HW 9		SLIP FRAME W/ SOUND GASKETING
117	116 MUSIC CLASSROOM	PAIRED FLUSH WOOD	6'-0"	7'-0"	SC WD	1 3/4"	D5	HM	SIM. J10	J10	F1	HW 15		W/ SOUND GASKETING
118	117 MUSIC OFFICE	FLUSH WOOD	3'-0"	8'-0"	SC WD	1 3/4"	D6	HM	SIM. J10	J10	F1	HW 8		
119	120 NEW CORRIDOR	FLUSH WOOD	3'-0"	7'-0"	SC WD	1 3/4"	D4	HM	SIM. J3	J3	F4	HW 8		
120	120 NEW CORRIDOR	FLUSH WOOD	3'-0"	7'-0"	SC WD	1 3/4"	D4	HM	SIM. J3	J3	F2	HW 8		
121	119 ATHLETIC STORAGE	PAIRED FLUSH WOOD	6'-0"	7'-0"	SC WD	1 3/4"	D3	HM	SIM. J3	J3	F1	HW 8		
122	OMIT													
123	122 ADA TOILET	FLUSH WOOD	3'-0"	8'-0"	SC WD	1 3/4"	D3	HM	SIM. J1	J1	F2	HW 3		DOOR IN EXISTING MASONRY WALL
124	123 STORAGE	FLUSH WOOD	3'-0"	8'-0"	SC WD	1 3/4"	D3	HM	SIM. J1	J1	F2	HW 8		DOOR IN EXISTING MASONRY WALL
125	124 STORAGE	FLUSH WOOD	3'-0"	7'-0"	SC WD	1 3/4"	D3	HM	SIM. J3	J3	F2	HW 8		
SECOND FLOOR														
201	201 CONTROL BOOTH	FLUSH SOLID CORE	3'-0"	7'-0"	WD	1 3/4"	D4	HM	SIM. J8	J8	F2	HW 16		
202	202 TECH ROOM	FLUSH SOLID CORE	3'-0"	7'-0"	WD	1 3/4"	D4	HM	SIM. J2	J2	F2	HW 8		
203	202 TECH ROOM	FLUSH METAL	2'-6"	6'-8"	HM	1 3/4"	D4	HM	SIM. J2	J2	F2	HW 8		
204	EAST FLY	FLUSH METAL	2'-6"	6'-8"	HM	1 3/4"	D4	HM	SIM. J11	J11	F2	HW 16		
205	WEST FLY	FLUSH METAL	2'-6"	6'-8"	HM	1 3/4"	D4	HM	SIM. J11	J11	F2	HW 16		

FINISH SCHEDULE

Room No.	Room Name	Floor	Base	Walls	Ceiling	Ceiling Height	Remarks
GROUND FLOOR							
G01	CORRIDOR NS	VCT	WOOD B	GW/B/PT, VEN PLYWD	GW/B/PT	13'-0"	
G01A	CLOSET A	CONC.	RUBBER	GW/B/PT	GW/B/PT	8'-0"	
G01B	CLOSET B	CONC.	RUBBER	GW/B/PT	GW/B/PT	8'-0"	
G01C	CLOSET C	CONC.	RUBBER	GW/B/PT	GW/B/PT	8'-0"	
G-01D	CLOSET D	CONC.	RUBBER	GW/B/PT	GW/B/PT	8'-0"	
G01E	CLOSET E	CONC.	RUBBER	GW/B/PT	GW/B/PT	8'-0"	
G01F	INSTRUMENT CLOSET	CONC.	RUBBER	GW/B/PT	GW/B/PT	8'-0"	
G01G	INSTRUMENT CLOSET	CONC.	RUBBER	GW/B/PT	GW/B/PT	8'-0"	
G02	ELECTRICAL CLOSET	CONC.	RUBBER	GW/B/PT	GW/B/PT	9'-0"	
G03	STORAGE	CONC.	RUBBER	GW/B/PT	GW/B/PT	VARIES	
G04	DANCE STORAGE	CONC.	RUBBER	GW/B/PT	ACT 1	9'-0"	
G05	OMIT						
G06	RECYCLING ROOM	CONC.	RUBBER	GW/B/PT	EXP/PT		PLYWOOD WAINSCOTING
G07	OFFICE	CONC.	RUBBER	GW/B/PT	ACT 1	12'-6"	PLYWOOD WAINSCOTING
G08	DRAMA ROOM	CONC.	WOOD A	GW/B/PT	ACT 1/ GWB	11'-6" / 13'-0"	SEE A-7.1
G09	ENTRY HALL	WOM	RUBBER	GW/B/PT	ACT 1		
G10	W/C	LINOLEUM	RUBBER	GW/B/PT	ACT 1	10'-0"	R-2
G11	WORKSHOP	CONC.	RUBBER	GW/B/PT	ACT 1	12'-0"	
G12	WEST WING	PLYWD	RUBBER	GW/B/PT	ACT 1		
G13	STAGE	PLYWD	RUBBER	GW/B/PT	ACT 1		
G14	EAST WING	PLYWD	RUBBER	GW/B/PT	ACT 1		
STAIR ONE	STAIR ONE	WOM/CONC.	RUBBER	GW/B/PT	EXP/PT		
FIRST FLOOR							
101	LOBBY	GT/CARP A	WOOD B	GW/B/PT, VEN PLYWD	GW/B/PT		
102	TOILET CORRIDOR	VCT / GT	WOOD B	GW/B/PT	GW/B/PT		
103	JANITORS CLOSET	VCT	RUBBER	GW/B/PT	ACT 1		R-2
104	OMIT						
105	WOMENS ROOM	CT	CT	CT	ACT 1		R-2
106	MENS ROOM	CT	CT	CT	ACT 1		R-2
107	THEATER VESTIBULE	CARP. B	WOOD B	VEN PLWD	GW/B/PT	8'-6"	
108	ENTRY	CARP. B	WOOD B	VEN PLWD	GW/B/PT		
109	THEATER	CARP. B	WOOD B	VEN PLWD	GW/B/PT		R1
110	CORRIDOR NS	GT	WOOD A	GW/B/PT	GW/B/PT	8'-8"	
111	OMIT						
112	EAST FLY	CONC.	RUBBER	GW/B/PT	EXP/PT		
113	WEST FLY	CONC.	RUBBER	GW/B/PT	EXP/PT		
114	MUSIC VESTIBULE	CARP. A	WOOD B	GW/B/PT	ACT 1		
115	MUSIC REHEARSAL	CARP. A	WOOD B	GW/B/PT	ACT 1		
116	MUSIC CLASSROOM	CARP. A	WOOD B	GW/B/PT	ACT 1		HOMASOTE & WHITE BDS
117	MUSIC OFFICE	CARP. A	WOOD B	GW/B/PT	ACT 1		
118	OMIT						
119	ATHLETIC STORAGE	VCT	RUBBER	GW/B/PT	EXP		
120	NEW CORRIDOR	VCT	RUBBER	GW/B/PT	EXP		
121	GVM	SPORT	TARAFLEX	GW/B/PT	EXP		VENTING BASE
122	ADA TOILET	LINOLEUM	RUBBER	GW/B/PT	GW/B/PT		
123	STORAGE	CONC.	RUBBER	GW/B/PT	EXP		
124	STORAGE	CONC.	RUBBER	GW/B/PT	EXP		
SECOND FLOOR							
201	CONTROL BOOTH	CARP. A	RUBBER	GW/B/PT	C-5	8'-0"	
202	TECH ROOM	CONC.	RUBBER	GW/B/PT	C-5		
203	EAST FLY LANDING	PLYWD	RUBBER	GW/B/PT	C-3		

FINISH SCHEDULE LEGEND

- FLOOR**
- EXIST. EXISTING TO REMAIN
 - VCT VCT
 - CARP. A CARPET Type A: BY COLLINS & AIKMAN
 - CARP. B CARPET Type B
 - LINOLEUM SHEET LINOLEUM FLOORING
 - WOM ALUMINUM FOOT GRILL (WALL - WALL)
 - GT GRANITE TILE
 - CONC. CONCRETE - SEALED
 - RT+R RUBBER TREADS AND RISERS AT STAIRS
 - PLYWD PLYWOOD FLOORING-PAINTED
 - SPORT NEW SPORTS FLOORING
- BASE**
- NONE NO BASE
 - CT CERAMIC TILE
 - RUBBER 4" RUBBER COVE BASE
 - WOOD A 1-PIECE RABBETED WOOD BASE-TYPE A
6" W/ GWB REVEAL. SEE DETAIL A-4.2
 - WOOD B 2-PIECE RABBETED WOOD BASE-TYPE B
6" W/ 1" TOP. SEE DETAIL A-6.2
- TARAFLEX**
- PROPRIETARY VENTING BASE FOR SPORTS FLOORING SYSTEM
- WALLS**
- EXIST. EXISTING TO REMAIN
 - GW/B/PT GYPSUM WALL BOARD-PAINTED
 - GW/B/PLWD GWB ON PLYWOOD-PAINTED
 - VEN PLYWD VENEER PLYWOOD-CLEAR FINISH
 - EXST. BRK EXISTING BRICK-CLEANED & SEALED
 - CMU/PT CMU-PAINTED
- TRIM**
- EXIST. EXISTING TO REMAIN
 - GW/B/PT GYPSUM WALL BOARD SOFFIT-PAINTED
 - WOOD PT WOOD TRIM-PAINTED
 - WOOD CR WOOD TRIM-CLEAR FINISH
- CEILING**
- EXIST. EXISTING TO REMAIN
 - EXP EXPOSED STRUCTURE
 - EXP/PT EXPOSED STRUCTURE-PAINTED
 - GW/B/PT GYPSUM WALLBOARD-PAINTED
 - ACT 1 SUSPENDED ACOUSTICAL TILE-TYPE 1
 - EXP/ABV EXPOSED STRUCTURE ABOVE
 - GW/B/SOF GYPSUM WALLBOARD SOFFIT-PAINTED
 - PLAS/PT PATCHED PLASTER-PAINTED
 - WOOD/SOF WOOD CEILING/SOFFIT-CLEAR FINISH
 - ACT 2 SUSPENDED GWB/ACT/SOUND INSULATED CLG-TYPE 2
- REMARKS**
- R-1 SEE INTERIOR ELEVATION FOR ADDITIONAL MATERIALS AND LIMITS OF MATERIALS
 - R-2 MOISTURE RESISTANT GWB AT ALL WALLS, CEILINGS

