Date: 06/26/13
Approved with Conditions

2 FIRST FLOOR ELECTRICAL/LIGHTING PLAN
SCALE: 1/4" = 1'-0"

3 SECOND FLOOR ELECTRICAL/LIGHTING PLAN
SCALE: 1/4" = 1'-0"

4 THIRD FLOOR ELECTRICAL/LIGHTING PLAN
SCALE: 1/4" = 1'-0"

1 LOWER LEVEL ELECTRICAL/LIGHTING PLAN
SCALE: 1/4" = 1'-0"

ELECTRICAL SCHEDULE

- DUPLEX 110v OUTLET
- GFI — DUPLEX 110v OUTLET W/ GROUND FAULT INTERRUPT
- EXT — DUPLEX 110v OUTLET INDICATED FOR EXTERIOR USE
- DUPLEX 110v FLOOR OUTLET
- QUAD 110v OUTLET
- REF — DEDICATED110v OUTLET
- 220 — DUPLEX 220v OUTLET
- GE — CABLE TV OUTLET
- TV — CABLE TV OUTLET
- $ — 2-WAY SWITCH W/ DIMMER
- 3 — 3-WAY SWITCH W/ DIMMER
- KP — LIGHITNG CONTROL KEYPAD
- JS — JAMB SWITCH
- TEL/ DATA
- TELEPHONE

GENERAL NOTES:

1. ALL LIGHT SWITCHES SHALL BE INSTALLED ON INSIDE OF ROOM BEING LIGHTED AND ON WALL ADJACENT TO DOOR HANDLE. TOP OF SWITCH COVERPLATE TO BE 48" ABOVE FINISH FLOOR, TYPICAL.
2. ALL LIGHTING TO BE DIMMABLE, EXCEPT TYPE C, D, F1, M, O, P AND Q. CONNECT TO DIMMER SWITCH BY LUTRON, TYPICAL.
3. LIGHTING LAYOUT AND DIMENSIONS ARE SHOWN FOR INTENT. EXISTING FRAMING SHALL REMAIN. ELECTRICAL CONTRACTOR SHALL PROPOSE REVISIONS TO THE LAYOUT BASED ON CONFLICTS WITH EXISTING FRAMING. ELECTRICAL CONTRACTOR AND BUILDER SHALL MEET WITH OWNER AND ARCHITECT PRIOR TO INSTALLATION OF LIGHTING TO REVIEW INTENT AND CONFIRM APPROVED LAYOUT.
4. CENTER LIGHTING FIXTURE TYPE 'D' IN CLOSET 003 AND 004, CENTER LIGHTING FIXTURE TYPE 'A1' AND TYPE 'F' IN WALK-IN CLOSET 203 AND TOILET 204.
5. ALL LIGHTING INDICATED ON FIRST FLOOR SHALL BE CONTROLLED BY LUTRON GRAPHIK EYE LOCATED IN KITCHEN PANTRY OR AS DETERMINED BY OWNER/ARCHITECT/ELECTRICAL CONTRACTOR/BUILDER. ELECTRICAL CONTRACTOR SHALL MEET WITH OWNERS AND ARCHITECT PRIOR TO INSTALLATION OF LIGHTING AND LIGHTING CONTROL WIRING TO REVIEW INTENT AND CONFIRM APPROVED LAYOUT.
6. ALL INDICATED KEYPADS SHALL BE DAISY CHAINED USING 'LUTRON YELLOW' WIRING AND HOME RUN TO GRAPHIK EYE LOCATED IN KITCHEN PANTRY AS INDICATED.
7. ALL LIGHTING SWITCHES AND ELECTRICAL OUTLETS ARE SHOWN FOR INTENT. ELECTRICAL CONTRACTOR SHALL MARK LOCATIONS ON WALL/STUD PRIOR TO INSTALLATION, FOR OWNER/ARCHITECT REVIEW AND SIGN-OFF.
8. SEE A101 AND A102 FOR LOCATION OF ADDITIONAL LIGHTING AT EXTERIOR PATIO AND DECK (TYPE E, O, P AND Q).

LIGHTING FIXTURE SCHEDULE

- A — 4" RECESSED LED DOWNLIGHT, GWB CEILING
- A1 — 4" RECESSED LED DOWNLIGHT, GWB CEILING , SHOWERLIGHT
- B — LINEAR LED LIGHT
- C — EXTERIOR WALL SCONCE
- D — LINEAR CLOSET LIGHT
- E — EXTERIOR WALL SCONCE
- F — SURFACE MOUNT CEILING LIGHT
- F1 — SURFACE MOUNT CEILING LIGHT
- G — SURFACE MOUNT PICTURE LIGHT
- H — 4" RECESSED LED DOWNLIGHT, WOOD CEILING
- H1 — 4" RECESSED LED DOWNLIGHT, WOOD CEILING, SHOWERLIGHT
- J — PENDANT LIGHT
- K — WALL SCONCE
- L — PENDANT LIGHT
- M — UNDER CABINET LED LIGHT
- N — EXHAUST FAN
- O — RECESSED STEP LIGHT (EXTERIOR)
- P — SURFACE MOUNT WALL SCONCE (EXTERIOR)
- Q — IN GROUND EXTERIOR LIGHT

Scott Simons Architects
Scott Simons Architects
75 York Street, Portland, Maine 04101
www.simonsarchitects.com
207.772.4656

STRUCTURAL ENGINEER
Becker Structural Engineers, Inc.
75 York Street
Portland, ME 04101
phone 207.897.1838
Nathan Merrill, PE
email: jim@beckerstructural.com

BUILDER
Steve Brann Building & Remodeling
39 South Freeport Road
Freeport, ME 04032
ph: 207.865.6674
alt: 207.671.7353
stevebrann@stevebrannbuilding.com

PROJECT NAME:

ALFOND RESIDENCE

RENOVATIONS & ADDITION
143 VAUGHAN STREET,
PORTLAND, ME 04101

SEAL:

THIS DRAWING IS THE PROPERTY OF SCOTT SIMONS ARCHITECTS (SSA) AND IS NOT TO BE COPIED OR REPRODUCED IN PART OR WHOLE.
2013 © SCOTT SIMONS ARCHITECTS, LLC

REVISION:

DATE OF ISSUE:	May 6, 2013
PROJECT NUMBER:	2013-0040 alfond renovation
STATUS:	100% Construction Documents

ELECTRICAL / LIGHTING PLANS

A111