Date: 06/26/13
Approved with Conditions
Inspector, Code Enforcement

FIRST FLOOR & DECK FRAMING PLAN

1/4"=1'-0"

NOTES:

1. INDICATES SPAN DIRECTION OF 3/4" ADVANTECH FLOOR SHEATHING.
2. TOP OF NEW FLOOR SHEATHING EL 8'-7"± V.I.F.
3. G/C NOTE-REROUTE EXIST ELECTRIC AND PLUMBING AS REQD FOR CHANNEL REINF INSTALLATION.

SECOND FLOOR/LOW ROOF FRAMING PLAN

1/4"=1'-0"

NOTES:

1. INDICATES SPAN DIRECTION OF 5/8" ROOF SHEATHING.
2. H-x INDICATES WOOD HEADER. SEE SCHEDULE THIS DWG
3. G/C SHALL PROVIDE TEMPORARY SHORING AS REQUIRED FOR BEARING WALL REMOVAL & BEAM INSTALLATIONS.

HEADER SCHEDULE		
MARK	SIZE	JAMB
H1	(2)2x6	(2)2x6: (1) KING & (1) JACK
H2	(3)1 3/4x5 1/2 LVL	(3)2x6: (2) KING & (1) JACK

FOUNDATION PLAN

1/4"=1'-0"

NOTES:

1. ALL ELEVATIONS INDICATED WITH RESPECT TO EXIST BASEMENT SLAB REF EL 0'-0".
2. (xx'-xx") INDICATES TOP OF FOOTING ELEVATION.
3. C.J. INDICATES CONTRACTION/CONSTRUCTION JOINT IN CONC SLAB. DEE DETAILS DWG S2.

Scott Simons Architects
75 York Street, Portland, Maine 04101
www.simonsarchitects.com
207.772.4656

STRUCTURAL ENGINEER
Becker Structural Engineers, Inc.
75 York Street
Portland, ME 04101
phone 207.897.1838
Nathan Merrill, PE
email: nathan@beckerstructural.com

BUILDER
Steve Brann Building & Remodeling
39 South Freeport Road
Freeport, ME 04032
ph: 207.865.6674
alt: 207.671.7353
stevebrann@stevebrannbuilding.com

PROJECT NAME:

ALFOND RESIDENCE

RENOVATIONS & ADDITION
143 VAUGHAN STREET,
PORTLAND, ME 04101

SEAL

THIS DRAWING IS THE PROPERTY OF SCOTT SIMONS ARCHITECTS (SSA) AND IS NOT TO BE COPIED OR REPRODUCED IN PART OR WHOLE.
2013 © SCOTT SIMONS ARCHITECTS, LLC

REVISION:

DATE OF ISSUE:	May 1, 2013
PROJECT NUMBER:	2013-0040 alfond renovation
STATUS:	100% Construction Documents

FOUNDATION & FLOOR FRAMING PLANS

S101