Inspections Division
Date: 12/13/16

Nov 23, 2016

# Specifications for Front Stair Railing for 58 Thomas Street

Dear Ms. Ross: Please add this to the building permit request filed Oct 31, 2016 … per your request.

Also, we would appreciate this being expiated as it involves a safety issue. We and are friends are getting older and the railing is needed before the arrival of snow and ice.

Facing the house, the railing will be on the right and be an exact match of the railing at 56 Thomas.

Measuring from at the first step the railing is 33” (measured from the center of the railing) above the first step. At the second to the last step this increases to 39”. The railing is attached to a post located at the final step (before the landing). It is exactly 6’ in length. From the post (at the landing), the railing is attached to the house. The height is 33” and length is 29”.

The material is round iron piping, or a similar material, painted black. It is attached with screws to the granite base, with screws to the wooden column and with screws to the brick façade of the house.

The pictures that you have should serve to answer any other questions. If not please contact me immediately. Thank you.

I am sending a copy of this letter to our contractor, Aaron Aspinall

John Gundersdorf

58 Thomas Street

207-899-2262

John.gundersdorf@gmail.com