



CARRIAGE HOUSE

1/4" = 1'-0"

STRUCTURAL NOTES

- ① EXISTING SLAB TO BE REINFORCED WITH 3" 4000 # FIBRE MESH CONCRETE
- ② EXISTING 2"X4" WALLS TO BE FURRED OUT TO 2X6, 16" O.C.
- ③ NEW CARRYING BEAM INSTALLED AT MID POINT OF 1<sup>st</sup> FL. CEILING JOISTS
- ④ ADDITIONAL 2"X 8'X 10' JOISTS TO BE INSTALLED 16" O.C.
- ⑤ NEW 2X8 CEILING JOIST/COLLAR TIES INSTALLED AT 2ND FL. CEILING