CITY OF PORTLAND, MAINE
RESURGAM
Reviewed for Code Compliance
Inspections Division
Approved with Conditions
Date: 03/02/16

CARRIAGE HOUSE
1/4" = 1'-0"

STRUCTURAL NOTES

1. EXISTING SLAB TO BE REINFORCED WITH 3" 4000# FIBRE MESH CONCRETE
2. EXISTING 2"X4" WALLS TO BE FURRED OUT TO 2X6, 16" O.C.
3. NEW CARRYING BEAM ISTALLED AT MID POINT OF 1st FL. CEILING JOISTS
4. ADDITIONAL 2"X 8"X 10' JOISTS TO BE INSTALLED 16" O.C.
5. NEW 2X8 CEILIN JOIST/COLLAR TIES INSTALLED AT 2ND FL. CEILING