PLAN
NORTH

NOTES:
1. PROVIDE SIMPSON JOIST HANGERS AT ALL JOIST ENDS, TYP. U.N.O.
2. WINDOW HEADERS SHALL BE (2)-2x10's w/ ½" PLYWOOD LAMS, U.N.O.
3. PROVIDE (3)-2x6 COLUMNS, U.N.O.

SECOND FLOOR FRAMING PLAN

SCALE: 1/2"=1'-0"

PLAN LEGEND

- BEARING WALL
- SHEAR WALL
- BEAM
- HSS COLUMN
- COLUMN FROM ABOVE
- COLUMN BELOW
- COLUMN ABOVE AND BELOW
- HOLD-DOWN

ROOF FRAMING PLAN

SCALE: 1/2"=1'-0"

PRINTED: Dec 01, 2015

Reviewed for Code Compliance
Inspections Division
Approved with Conditions
Date: 03/02/16

CASCO BAY ENGINEERING
424 Fore Street
Portland, ME 04101
Phone 207.842.2800
Fax 207.842.2828
www.cascobayengineering.com

CLIENT:
JOHN MULDOON

13 COLUMBUS AVE
S PORTLAND ME 04106

PRELIMINARY
NOT FOR CONSTRUCTION

AKERMANN
PORTLAND ME

RESIDENTIAL

ISSUED

No.	DESCRIPTION	DR. BY	CKD. BY	DATE

SHEET TITLE:
SECOND FLOOR AND ROOF FRAMING PLANS

DESIGNED:	ED
DRAWN:	CD
DATE:	11-23-15
PROJECT NUMBER:	15-196

S1.0