

DISPLAY THIS CARD ON PRINCIPAL FRONTAGE OF WORK



# CITY OF PORTLAND BUILDING PERMIT



**This is to certify that**  
SEASIDE PARTNERS LLC

**Located at**  
107 VAUGHAN ST

**PERMIT ID:** 2018-00261    **ISSUE DATE:** 04/03/2018    **CBL:** 062 D016001

has permission to **After the fact for finishing basement. Adding one non-bearing 2x4 stud wall to separate bath from mechanical room. Two non-bearing 2x4 wood walls added to create laundry room.VCT added to existing slab.**

provided that the person or persons, firm or corporation accepting this permit shall comply with all of the provisions of the Statutes of Maine and of the Ordinances of the City of Portland regulating the construction, maintenance and use of the buildings and structures, and of the application on file in the department.

Notification of inspection and written permission procured before this building or part thereof is lathed or otherwise closed-in. 48 hour notice is required.

A final inspection must be completed before this building or part thereof is occupied. If a certificate of occupancy is required, it must be procured prior to occupancy.

N/A

/s/ Michael Russell, MS, Director

**Fire Official**

**Building Official**

**THIS CARD MUST BE POSTED ON THE STREET SIDE OF THE PROPERTY  
THERE IS A PENALTY FOR REMOVING THIS CARD**

*Approved Property Use - Zoning*

*Building Inspections*

*Fire Department*

BUILDING PERMIT INSPECTION PROCEDURES  
Please call 874-8703  
or email: [buildinginspections@portlandmaine.gov](mailto:buildinginspections@portlandmaine.gov)

**Check the Status of Permit or Schedule an Inspection at  
<http://www.portlandmaine.gov/planning/permitstatus.asp>**

With the issuance of this permit, the owner, builder or their designee is required to provide adequate notice to the City of Portland Inspections Division for the inspections listed below. Appointments must be requested 48 to 72 hours in advance. The inspection date will need to be confirmed by this office.

- **Please read the conditions of approval that are attached to this permit.**
- **Permits expire in 6 months if the project is not started or ceases for 6 months.**
- **If the inspection requirements below are not followed, then additional fees may be incurred due to the issuance of a "Stop Work Order" and subsequent release to continue.**
- **Per Section 107.3.1 of the Maine Uniform Building and Energy Code (MUBEC), one set of printed approved stamped construction documents will be kept at the site of work and open to inspection by building officials.**

### **REQUIRED INSPECTIONS:**

Close-in Plumbing/Framing

Electrical Close-in

Final Inspection

Final - Electric

The project cannot move to the next phase prior to the required inspection and approval to continue.

If the permit requires a certificate of occupancy, it must be paid and issued to the owner or designee before the space may be occupied.

<b>City of Portland, Maine - Building or Use Permit</b>		<b>Permit No:</b> 2018-00261	<b>Date Applied For:</b> 02/27/2018	<b>CBL:</b> 062 D016001
389 Congress Street, 04101 Tel: (207) 874-8703, Fax: (207) 874-8716				
<b>Proposed Use:</b> Same	<b>Proposed Project Description:</b> After the fact for finishing basement. Adding one non-bearing 2x4 stud wall to separate bath from mechanical room. Two non-bearing 2x4 wood walls added to create laundry room. VCT added to existing slab.			
<b>Dept:</b> Fast Track <b>Status:</b> Approved w/Conditions <b>Reviewer:</b> Keri Ouellette <b>Approval Date:</b> 03/14/2018				
<b>Note:</b>				<b>Ok to Issue:</b> <input checked="" type="checkbox"/>
<b>Conditions:</b>				
<p>1) Finished rooms shall not be used for sleeping rooms if they do not comply with the requirements of IRC Section R310 for Emergency Escape and Rescue Openings.</p> <p>2) Safety Glazing for hazardous location shall comply with § R308.4 of the IRC, 2009 (MUBEC).  Glazing in enclosures is required for or walls facing hot tubs, whirlpools, saunas, steam rooms, bathtubs and showers where the bottom exposed edge of the glazing is less than 60 inches measured vertically above any standing or walking surface. Exception: Glazing that is more than 60 inches, measured horizontally and in a straight line, from the waters edge of a hot tub, whirlpool or bathtub.  Bathrooms shall have a minimum ceiling height of 6 feet 8 inches at the center of the front clearance area for fixtures as shown in Figure R307.1. The ceiling height above fixtures shall be such that the fixture is capable of being used for its intended purpose. A shower or tub equipped with a showerhead shall have a minimum ceiling height of 6 feet 8 inches above a minimum area 30 inches by 30 inches at the showerhead.   Bathroom fixtures shall have a minimum front clearance of 24 inches. Toilets shall be located a minimum of 15 inches from the centerline of the fixture to the adjacent side wall or plumbing fixture at side.   Mechanical or natural ventilation is required in the bathroom.  Carbon Monoxide (CO) alarms shall be installed in each area within or giving access to bedrooms. That detection must be powered by both the electrical service (plug-in or hardwired) in the building and battery.   Hardwired (non- ionization detection technology) interconnected battery backup smoke alarms shall be installed in each bedroom, protecting the bedrooms, and on every level.   R307.2 Bathtub and shower spaces. Bathtub and shower floors and walls above bathtubs with installed shower heads and in shower compartments shall be finished with a nonabsorbent surface. Such wall surfaces shall extend to a height of not less than 6 feet (1829 mm) above the floor.   The clear space in front of any water closet or bidet shall be not less than twenty-four (24) inches (610 mm).   Fireblocking is required to provide a cut off of all concealed draft openings (both vertical and horizontal) in combustible construction, see Sec. R302.11.</p> <p>3) The review of this permit did not include a review or confirmation of the zoning legal use. It is only approving the specific work described in the plans and forms submitted. The current use of the property may be found to be unlawful.</p> <p>4) Separate permits are required for any electrical, plumbing, sprinkler, fire alarm, HVAC systems, heating appliances, including pellet/wood stoves, commercial hood exhaust systems, fire suppression and fuel tanks. Separate plans may need to be submitted for approval as a part of this process.</p> <p>5) This is being issued with the understanding that as a fast track, the owner is responsible for scheduling inspections for the work being done and the inspector may require modifications to the work that has been completed if it does not meet code.</p> <p>6) This permit is being approved on the basis of plans submitted. Any deviations shall require a separate approval before starting that work.</p>				
<b>Dept:</b> Historic <b>Status:</b> Approved w/Conditions <b>Reviewer:</b> Deborah Andrews <b>Approval Date:</b> 04/02/2018				
<b>Note:</b>				<b>Ok to Issue:</b> <input checked="" type="checkbox"/>
<b>Conditions:</b>				

**PERMIT ID:** 2018-00261

**Located at:** 107 VAUGHAN ST

**CBL:** 062 D016001

1) Any exterior alterations associated with project, including installation of exterior vent(s), requires approval under historic preservation ordinance standards.