



where possible, original structural framing will be maintained, mated to new wall construction

standard 2x4 construction studs on 15" centers

standard PEX plumbing

19 Thomas St 3rd Fl Bathroom framing and construction detail

nominal 3/4" tile backer in shower area

nominal 3/4" drywall replaces original plaster and lath on all walls