

19 Bramhall street Portland Me.

Back Deck Specifications

1. Deck length.....50"
2. Deck width.....48"
3. Deck Height.....25"-26"
4. Include 2 steps
5. Step tread.....11 1/4 "
6. Step riser.....7"
7. Step nosing.....1"
8. Railing height.....36"
9. Baluster spacing3"
10. Baluster.....1.25"x1.25"
11. Deck Posts (Cedar)4x4"
12. Decking, (spruce or P.T.)5/4
13. Framing , (Pressure Treated) 12" O/C.....2x6

Deck skirt will be vertical 1x2 spaced at 1" intervals

Top rail will be custom designed to match (Brosco AT201Z)

Post caps will also match Brosco style (AT99070000W)

Stair stringer will be cased in pine to match riser.