SWT
01.12.2008
For Construction

DOOR SCHEDULE

MARK	SIZE W	SIZE HT	SIZE THK	Quantity	Model #	Manufacturer	Type	Material	Glazing	NOTES
1	2'-6"	6'-8"	0'-1 3/8"	1			swing	solid wd		
2	2'-6"	6'-8"	0'-1 3/8"	1			swing	solid wd		
3	2'-6"	6'-8"	0'-1 3/8"	1			swing	solid wd		
4	2'-0"	6'-8"	0'-1 3/8"	1			swing	solid wd		
E1	3'-0"	8'-4 1/2"	0'-1 3/4"	2			french	wd / glass	low-e	

WINDOW SCHEDULE

ID	R.O. Size VIF Width	R.O. Size VIF Height	Quantity	Type	Model #	Manufacturer	Material	Glazing	Egress	Tempered	NOTES
W1	2'-10"	3'-8"	1	2-over-2, Double-Hung	Tiltpac	Marvin		Clear, Low-E, Argon			
W2	2'-10"	3'-4"	1	Ditto	Ditto	Ditto		Ditto			
W3	2'-10"	3'-4"	1	Ditto	Ditto	Ditto		Ditto			
W4	2'-10"	3'-4"	1	Ditto	Ditto	Ditto		Ditto			
W5	2'-10"	3'-8"	1	Ditto	Ditto	Ditto		Ditto			
W6	2'-4"	2'-9"	1	Ditto	Ditto	Ditto		Ditto			
W7	2'-4"	2'-9"	1	Ditto	Ditto	Ditto		Ditto			
W8	2'-10"	3'-8"	1	Ditto	Ditto	Ditto		Ditto			
W9	2'-10"	3'-8"	1	Ditto	Ditto	Ditto		Ditto			
W10	2'-10"	3'-8"	1	Ditto	Ditto	Ditto		Ditto			
W11	2'-10"	3'-8"	1	Ditto	Ditto	Ditto		Ditto			
W12	2'-4"	3'-8"	1	Ditto	Ditto	Ditto		Ditto			

NOTES:

1. New sashes to all 3rd. floor window. Refer to window schedule.
2. New casing & sill trim to all 3rd floor windows.
3. New casing trim to all 3rd floor doors.
4. New baseboard trim throughout 3rd floor.
5. New Graber Performance Supreme 1" aluminum horizontal blinds to all 3rd floor windows. Standard color to be selected. Wand tilt. Cordless lift. Privacy slat. Graber 1"high x 1-1/2" wide head track to be fully recessed in to existing head liner. Base to be flush with face of liner.

1 3rd Floor
SCALE: 1/4" = 1'-0"

2 2nd Floor
SCALE: 1/4" = 1'-0"

KAPLAN THOMPSON ARCHITECTS
424 Fore St., Portland, ME 04101
207-842-2888 fax:842-2828

Project:
Sweet Residence
Alterations for Julian Sweet
187 Vaughan St. #2
Portland, ME 04102

Drawing: Proposed Plan
Scale:
Drawn by: RTL
Date: January 12, 2009
Revised: #Rev. A

A-1.2