



Reviewed for Code Compliance
Inspection Division
Approved with Conditions
Date: 06/04/15

scott simons architects
designed for human potential

75 York Street
Portland, Maine 04101
simonsarchitects.com
207.772.4656

PROJECT NAME:
PINE ST RESIDENCE

RENOVATIONS
157-159 PINE STREET
PORTLAND, ME 04101



THIS DRAWING IS THE PROPERTY OF SCOTT SIMONS ARCHITECTS (SSA) AND IS NOT TO BE COPIED OR REPRODUCED IN PART OR WHOLE. 2015 © SCOTT SIMONS ARCHITECTS, LLC


REVISION:

1	DATE
2	DATE
3	DATE
4	DATE
5	DATE
6	DATE

DATE OF ISSUE: APRIL 17, 2015
 PROJECT NUMBER: 2015-0010
 STATUS: PERMIT SET

BASEMENT DEMOLITION PLAN

AD100



EXTERIOR DEMOLITION LIMIT OF WORK

APPROXIMATE PORTION OF WALL TO BE REMOVED. SEE PLANS FOR MORE INFO.


2 ELEVATION DIAGRAM
SCALE: 1/4" = 1'-0"

DEMOLITION KEY NOTES:

- 1 REMOVE EXISTING DECK, DECK ROOF STRUCTURE, STAIRS, AND RAILINGS. SALVAGE ALL COMPONENTS FOR OWNER REUSE/DONATION.
- 2 REMOVE EXISTING GUARDRAILS
- 3 REMOVE EXISTING BRICK WALL AND FINISHES.
- 4 REMOVE EXISTING DOOR, FRAME AND HARDWARE. SALVAGE DOOR AND HARDWARE FOR OWNER REUSE.
- 5 REMOVE EXISTING STAIRS, HANDRAIL AND FRAMING.
- 6 REMOVE EXISTING WOOD STUD WALL AND FINISHES
- 7 REMOVE EXISTING PLUMBING FIXTURES, SALVAGE FOR OWNER REUSE/DONATION.
REMOVE EXISTING CABINETS, SINK, APPLIANCES, AND ALL ASSOCIATED PLUMBING/WIRING BACK TO SOURCE. SALVAGE ALL CABINETS, HARDWARE, PLUMBING FIXTURES AND APPLIANCES FOR OWNER REUSE/DONATION.
- 8 REMOVE EXISTING WOOD FLOOR AND FRAMING
- 9 REMOVE EXISTING TILE FLOOR, DOWN TO SUBFLOOR.
- 10 REMOVE EXISTING WOOD FLOOR, DOWN TO SUBFLOOR.
- 11 REMOVE STRUCTURAL POST AND ANY ASSOCIATED COVES AND/OR TRIM
- 12 REMOVE EXISTING AIR SUPPLY DUCTING AND GRILLES, BACK TO SOURCE.
- 13 REMOVE EXISTING CLOSET SHELVING.
- 14 REMOVE EXISTING SHOWER, ENCLOSURE, TILE AND ALL ASSOCIATED PLUMBING/FIXTURES. REMOVE PLUMBING BACK TO SURFACE AND CAP.
- 15 REMOVE EXISTING CEILING AND FRAMING COMPONENTS
- 16 REMOVE EXISTING HVAC SYSTEM AND ALL DUCTING TO AND FROM SOURCE
- 17 REMOVE EXISTING WINDOW, FRAME AND HARDWARE. SALVAGE FOR OWNER
- 18 REMOVE EXISTING SKYLIGHT, FRAME AND HARDWARE. SALVAGE FOR OWNER
- 19 PROVIDE WALL PENETRATION FOR FUTURE APPLIANCE VENT
REMOVE STRUCTURAL LVL AND FASTENING COMPONENTS. CUT FRAMING BACK TO RECEIVE NEW STRUCTURAL BEAM. SEE STRUCTURAL FOR MORE INFO.
- 20 BEAD BLAST EXISTING STRUCTURAL BEAM TO REMOVE ALL PAINT

GENERAL DEMOLITION NOTES:

1. ALL WORK TO BE SEQUENCED, PHASED AND SCHEDULED WITH OWNER.
2. G.C. TO PROTECT ADJACENT AREAS NOT AFFECTED BY CONSTRUCTION.
3. G.C. TO FIELD VERIFY ALL CONDITIONS PRIOR TO BIDDING AND CONSTRUCTION.
4. ALL EXISTING MATERIALS NOTED TO BE REMOVED SHALL BE PROPERLY DISPOSED OF BY G.C. UNLESS OTHERWISE NOTED. OWNER RESERVES THE RIGHT TO RETAIN AN ITEM NOTED FOR DEMOLITION.
5. G.C. SHALL COORDINATE EXTENT OF ALL DEMOLITION WORK WITH NEW CONSTRUCTION.
6. ALL ELECTRICAL, PLUMBING AND MECHANICAL LOCATED IN WALLS AND CEILINGS NOTED TO BE REMOVED SHALL BE EITHER REMOVED BACK TO SOURCE OR LOCATED OUT OF HARM'S WAY FOR RELOCATION IN NEW CONSTRUCTION. G.C. TO COORDINATE.
8. REMOVE EXISTING LIGHTING, SWITCHES, ELECTRICAL OUTLETS, AND MISC. WIRING BACK TO SOURCE IN ALL AREAS WITHIN SCOPE OF RENOVATION U.N.O.
9. EXISTING PLUMBING, ELECTRICAL AND GAS ITEMS IN BASEMENT TO REMAIN, U.N.O
10. G.C. TO PROVIDE TEMPORARY STRUCTURAL BRACING AND FRAMING AS REQUIRED DURING DEMOLITION



1 BASEMENT FLOOR PLAN
SCALE: 1/4" = 1'-0"