

DISPLAY THIS CARD ON PRINCIPAL FRONTAGE OF WORK



CITY OF PORTLAND BUILDING PERMIT



This is to certify that
40 WEST STREET LLC

Located at
40 WEST ST

PERMIT ID: 2016-02803 **ISSUE DATE:** 02/06/2017 **CBL:** 063 H004001

has permission to **For the installation of a fire alarm system for the whole building.**
provided that the person or persons, firm or corporation accepting this permit shall comply with all of the provisions of the Statues of Maine and of the Ordinances of the City of Portland regulating the construction, maintenance and use of the buildings and structures, and of the application on file in the department.

Notification of inspection and written permission procured before this building or part thereof is lathed or otherwise closed-in. 48 hour notice is required.

A final inspection must be completed before this building or part thereof is occupied. If a certificate of occupancy is required, it must be procured prior to occupancy.

/s/ David Petruccelli

/s/ Michael Russell, MS, Director

Fire Official

Building Official

**THIS CARD MUST BE POSTED ON THE STREET SIDE OF THE PROPERTY
THERE IS A PENALTY FOR REMOVING THIS CARD**

Approved Property Use - Zoning
not determined

Building Inspections

Fire Department

BUILDING PERMIT INSPECTION PROCEDURES
Please call 874-8703
or email: buildinginspections@portlandmaine.gov

**Check the Status of Permit or Schedule an Inspection at
<http://www.portlandmaine.gov/planning/permitstatus.asp>**

With the issuance of this permit, the owner, builder or their designee is required to provide adequate notice to the City of Portland Inspections Division for the inspections listed below. Appointments must be requested 48 to 72 hours in advance. The inspection date will need to be confirmed by this office.

- **Please read the conditions of approval that are attached to this permit.**
- **Permits expire in 6 months if the project is not started or ceases for 6 months.**
- **If the inspection requirements below are not followed, then additional fees may be incurred due to the issuance of a "Stop Work Order" and subsequent release to continue.**
- **Per Section 107.3.1 of the Maine Uniform Building and Energy Code (MUBEC), one set of printed approved stamped construction documents will be kept at the site of work and open to inspection by building officials.**

REQUIRED INSPECTIONS:

Final - Fire

The project cannot move to the next phase prior to the required inspection and approval to continue.

If the permit requires a certificate of occupancy, it must be paid and issued to the owner or designee before the space may be occupied.

City of Portland, Maine - Building or Use Permit		Permit No: 2016-02803	Date Applied For: 10/31/2016	CBL: 063 H004001
389 Congress Street, 04101 Tel: (207) 874-8703, Fax: (207) 874-8716				
Proposed Use: Same: Multi-family apartment building	Proposed Project Description: For the installation of a fire alarm system for the whole building.			
Dept: Zoning Status: Approved w/Conditions Reviewer: Ann Machado Approval Date: 02/02/2017 Note: Ok to Issue: <input checked="" type="checkbox"/> Conditions: 1) The review of this permit did NOT include a review or confirmation of the zoning legal use. It is only approving the specific work described in the plans and forms submitted by the applicant. The current use of the property may be found to be unlawful. 2) ANY exterior work requires a separate review and approval thru Historic Preservation. This property is located within an Historic District.				
Dept: Fire Status: Approved w/Conditions Reviewer: David Petrucci Approval Date: 02/06/2017 Note: Ok to Issue: <input checked="" type="checkbox"/> Conditions: 1) All fire alarm records required by NFPA 72 should be stored in an approved cabinet located at the FACP labeled "FIRE ALARM RECORDS". 2) Fire protection systems shall be maintained. If system is to be off line over 4 hours a fire watch shall be in place. Dispatch notification required 874-8576. 3) All smoke alarms shall be photoelectric. 4) The fire alarm technician shall be present for the fire inspection. System acceptance and commissioning must be coordinated with alarm and suppression system contractors and the Fire Department. Call 874-8400 to schedule. 5) Through-penetrations and membrane penetrations in fire walls, fire barrier walls, and fire resistance rated horizontal assemblies shall be protected by firestop systems or devices in conformance with NFPA 101:8.3.5 (ASTM E 814 or ANSI/UL 1479). Providing firestop labels at each firestop system or device and an onsite manual containing the detail for each firestop system or device used for the project will streamline final inspection approvals. 6) All smoke detectors shall be photoelectric. 7) The installation shall comply with the following: City of Portland Chapter 10, Fire Prevention and Protection; NFPA 1, Fire Code (2009 edition), as amended by City Code; NFPA 101, Life Safety Code (2009 edition), as amended by City Code; City of Portland Fire Department Rules and Regulations; NFPA 72, National Fire Alarm and Signaling Code (2010 edition), as amended by Fire Department Rules and Regulations; and NFPA 70, National Electrical Code (2011 edition) as amended by the State of Maine 8) In field installation shall be installed per code as conditions dictate. 9) Single-station Carbon Monoxide (CO) alarms powered by the building's electrical service with battery backup are required within the dwelling units. CO alarms shall be installed in the following locations: (1) Outside each separate dwelling unit sleeping area in the immediate vicinity of the bedrooms (2) On every occupiable level of the dwelling unit, including basements, excluding attics and crawl spaces New CO alarms shall be hardwired. 10) Records cabinet, FACP, annunciator(s), and pull stations shall be keyed alike. 11) Supervising Station monitoring for addressable fire alarm systems shall be by point. 12) A 4100 series Knox Box is required.				

13 A master box connection and drill switch is required. AES Zones shall be:

1. Water flow
2. City Disconnect: Water flow
3. Pull stations and detectors
4. City Disconnect: Pull stations and detectors
5. Not assigned
6. Not assigned
7. Not assigned
8. AES tamper switch

14 Notice: The first scheduled final inspection fee is at no charge. Additional inspections shall be billed at \$75 for each inspector.

15 The approved plans with the Building Department Approved stamp shall be maintained on site for inspection.

16 Hardwired single-station smoke alarms are required within the dwelling units. Smoke alarms shall be installed in the following locations:

- (1) All sleeping rooms
- (2) Outside each separate sleeping area, in the immediate vicinity of the sleeping rooms
- (3) On each level of the dwelling unit, including basements.

New smoke alarms shall be photoelectric powered by the building's electrical service with battery backup.

17 The fire alarm system shall have a new fire alarm inspection sticker.