

CITY OF PORTLAND
 FIRE PREVENTION BUREAU
 380 Congress Street, Portland, Maine 04101
 fireprevention@portlandmaine.gov
 (207) 874-8400

NOTICE OF VIOLATION AND ORDER TO CORRECT

August 22, 2017

Responsible Party 1: Chase Patricia 210 SAINT JOHN ST PORTLAND, ME 04102		
Location 210 ST JOHN ST	CBL 064 A010001	Inspection Date 7/27/2017
Inspector Curtis Magnuson	Inspection Type FP Routine Inspection	Status Failed

The City of Portland Fire Department inspected this property, and found the fire and life safety code violations listed below, which you are hereby ordered to correct. You must propose a date of completion to remedy each violation, a final date of completion, and a date of re-inspection.

You must send this form to the Fire Prevention Bureau no later than 9/15/2017.

Your failure to submit a plan of action by the date provided, or to correct any violation within the applicable time frame, may result in legal action against you, the imposition of civil penalties, and the pursuit of other legal remedies.

Violation	Proposed Date of Completion
NFPA 101- 7.5.1.1 AND 7.5.1.1.1 OBSTRUCTED EGRESS; Exits shall be located and exit access shall be arranged so that exits are readily accesible at all times (7.5.1.1). Where exits are not immediately accessible from an open floor area, continuous passageways, aisles, or corridors leading directly to every exit shall be maintained and shall be arranged to provide access for each occupant to not less than two exits by separate ways of travel, unless otherwise provided in 7.5.1.1.3 and 7.5.1.1.4 (7.5.1.1.1). No storage allowed in the stairwells going to the 2nd and 3rd floor apartments.	
NFPA 101- 7.2.1.8.1 FIRE DOOR(S) MUST SELF-CLOSE; A door leaf normally required to be kept closed shall not be secured in the open position at any time and shall be self-closing or automatic-closing in accordance with 7.2.1.8.2, unless otherwise permitted by 7.2.1.8.3. Basement and third floor apartment doors.	
NFPA 101- 7.2.2.4.1.1 STAIRS SHALL HAVE HANDRAILS; Stairs and ramps shall have handrails on both sides, unless otherwise permitted in 7.2.2.4.1.5 or 7.2.2.4.1.6. Basement stairwell	
NFPA 720- 5.5.6.1 CO ALARMS REQUIRED; The performance, location, and mounting of notification appliances used to initiate or direct action, evacuation or relocation of the occupants, or for providing information to occupants or staff, shall comply with the requirements of Chapter 6. 120 volt Carbon Monoxide alarms are required in every unit including the basement.	IMMEDIATELY install temporary alarms where required. Your signature below indicates that temporary alarms have already been installed.

Violation	Proposed Date of Completion
<p>NPFA 101- 31.3.4.5.1 SMOKE DETECTOR VIOLATION; In buildings other than those equipped through out with an existing, complete automatic smoke detection system, smoke alarms shall be installed in accordance with 9.6.2.10, as modified by 31.3.4.5.2, outside every sleeping area in the immediate vicinity of the bedrooms on all levels of the dwelling unit, including basements.</p> <p>All the smoke detectors appeared to be greater than 10 years old. If the current detector is not functioning then replace with a hardwired smoke alarm.</p>	
<p>NPFA 101- 31.3.4.5.1 SMOKE DETECTOR VIOLATION; In buildings other than those equipped through out with an existing, complete automatic smoke detection system, smoke alarms shall be installed in accordance with 9.6.2.10, as modified by 31.3.4.5.2, outside every sleeping area in the immediate vicinity of the bedrooms on all levels of the dwelling unit, including basements.</p> <p>3rd floor apartment has a smoke detector that needs to have a battery installed.</p>	
<p>NPFA 101- 590.6 DISCONTINUE USE OF EXTENSION CORDS; Ground-fault protection for personnel for all temporary wiring installations shall be provided to comply with 590.6(A) and (B). This section shall apply only to temporary wiring installations used to supply temporary power to equipment used by personnel during construction, remodeling, maintenance, repair, or demolition of buildings, structures, equipment, or similar activities.</p> <p>3rd floor apartment hall and 2nd floor apartment in the kitchen.</p>	
<p>NFPA 80- ANNEX D.4 1-HOUR FIRE DOORS ASSEMBLIES REQ; Listings are provided for floor fire door assemblies that are installed in fire-rated floor-ceiling or roof-ceiling assemblies that have been tested in accordance with the methods described in NFPA 288. The listing indicates the fire-rated assembly and the hourly rating (3 hours, 2 hours, 1.5 hours, 1 hour, .75 hours) for which the door can be permitted to be used so that access to the space above the ceiling or to the floor above can be provided without adversely affecting the fire resistance rating of the entire assembly. The listing provides limitations on the maximum size of an individual door opening and the total area of all door openings permitted for each 100 square feet of floor or ceiling.</p> <p>1) Need two fire doors in the front hall that services the business on the first floor. One of these doors maybe avoided if one is removed and the wall enclosed. 2) 2nd floor apartment, rear stairwell entry door. All fire doors must self-close!</p>	
<p>CITY OF PORTLAND RULES AND REGS- CHAPTER 4.6 LABEL UNIT DOORS; 4.6 Commercial suites shall be designated as approved by the FD. In single floor buildings letter designations shall be acceptable. 4.6.1 Residential units shall be designated using numericals. 4.6.2 The first numerical of each residential unit shall be the floor designation. 4.6.3 In single floor buildings the floor designation shall be omitted.</p> <p>Label the apartment entry doors with the units number</p>	
<p>FINAL DATE OF COMPLETED VIOLATION(S)</p>	<p>___/___/___</p>
<p>FIRE PREVENTION BUREAU RE-INSPECTION OF COMPLETED VIOLATION(S)</p>	<p>___/___/___</p>

The Bureau reserves the right to reject or modify any proposed plan of action, and may require evidence of sufficient financial and technical capacity to complete the proposed plan. Please contact the Bureau with any questions.

VIOLATOR CERTIFICATION

I agree to remedy the violations listed within the timeframes provided. If I require additional time to comply, I understand that I must contact the Fire Prevention Bureau prior to the deadline to request an extension, which is entirely within the Bureau's discretion to grant or deny.

I further understand that it is my responsibility to schedule a reinspection of my property once the violations have been remedied to do so. My failure to schedule a reinspection shall be deemed an admission that the violations have not been remedied.

If I fail to comply with this agreement, I understand that I am liable for penalties pursuant to the City of Portland Code of Ordinances §§ 1-15 and 10-25, and 30-A M.R.S. § 4452 and may be subject to further legal action.

Date

Responsible Party

Date

Responsible Party

SEEN AND AGREED

Date

Fire Prevention Bureau