



MECHANICAL KEYNOTES	
NOTE	DESCRIPTION
D01	REMOVE EXISTING CEILING EXHAUST GRILLE
D02	EXHAUST DUCTWORK SHALL REMAIN FOR RECONNECTION
D03	EXHAUST RISER SHALL REMAIN
D04	REMOVE EXISTING EXHAUST DUCTWORK
D05	REMOVE EXISTING EXHAUST DUCTWORK AND CAP
D06	REMOVE EXISTING SUPPLY DIFFUSER
D07	REMOVE EXISTING SUPPLY & RETURN DUCTWORK
D08	EXHAUST RISER SHALL BE CONVERTED TO A MAKE-UP RISER
D09	REMOVE EXISTING GUEST LAUNDRY DRYER VENT
D10	CAP EXHAUST RISER ABOVE CEILING
D11	REMOVE EXISTING EXHAUST FAN
D12	REMOVE EXISTING PTAC
D13	LAUNDRY EXHAUST SYSTEM SHALL REMAIN
D14	EXISTING PTAC SHALL REMAIN
D15	REMOVE EXISTING AIR SYSTEM, CONDENSER AND SYSTEM PIPING
D16	REMOVE EXISTING WALL HEATER AND PATCH WALL TO MATCH EXISTING
D17	REMOVE & REPLACE EXISTING CEILING EXHAUST FAN
D18	REMOVE EXISTING AIR CURTAIN
D22	REMOVE EXISTING WALL FAN & PATCH WALL TO MATCH EXISTING
D23	REMOVE & REPLACE EXISTING LOUVER AND DAMPER

1 ENLARGED LOBBY DEMOLITION PLAN
1/4" = 1'-0"

Project:
PORTLAND LaQUINTA INN & SUITES - LQ #2049 RENOVATION

Project Owner:
LQ MANAGEMENT, LLC

909 HIDDEN RIDGE, SUITE 600 IRVING, TEXAS 75038

Architect:
BMA
 Architectural Group
 Professional Corporation
 Architects ■ Designers ■ Planners
 12 Middle Street
 Amherst, New Hampshire 03031
 TEL 603 673 1991 FAX 603 672 1385
 www.bmaworld.com

Seal:

 STATE OF MAINE
 JES, INC.
 No. 5378
 LICENSED PROFESSIONAL ENGINEER

ENGINEER:
JES, INC.
 INTEGRATED ENGINEERED SYSTEMS, INC.
 Δ MECH. DESIGN
 Δ ENERGY MGT.
 Δ INDOOR AIR QUALITY
 P.O. BOX 657
 AUBURN, N.H. 03032
 Tel: (603) 625-1346
 Fax: (603) 625-8456

REVISIONS

Job Number: J799
 Drawn By: CLB
 Checked By: JK
 Phase: Lobby and ADA Documents

Drawing Title:
ENLARGED LOBBY MECHANICAL DEMOLITION PLAN

SHEET NUMBER:
MD-300

DATE: 10 APRIL 2017