

## General Notes:

This sign is to be installed in accordance with the requirements of Article 600 of the National Electrical Code.

1) Grounded and bonded per NEC 600.7/NEC 250 2) Existing branch circuit in compliance with

NEC 600.5, not to exceed 20 amps 3) Sign is to be UL listed per NEC 600.3

4) UL disconnect switch per NEC 600.6- required per sign component before leaving manufacturer\* \*For multiple signs, a disconnect is permitted but not required for each section


## 11'-4" [136"] [132"] 11'-0" PAINTS



## Specifications: Wall Sign, Lexan Face

## 1. Existing Facade: Brick

- 2. 0.080" Aluminum sign cabinet painted to match PMS 307C
- 3. 2" x 2" Aluminum angle retainers painted to match PMS 307C
- 4. 3/16" White Lexan face with first surface digitally printed vinyl
- 5. Sign cabinet contains White LEDs and transformers
- 6. Disconnect switch UL Outdoor rated toggle type w/ neoprene boot per NEC 600-6
- 7. Primary electrical feed
- 8. Mounting hardware; 3/8" Sleeve anchor





LED IIIum

Scale: N.T.S.

PPG PAINTS	Client: PPG Site #: PP-8289 Address: 973 Congress Street Portland, ME 04102	09/30/2014 Original Rendering   11/18/2014 Updated for permitting	SD AW AW AW AW AW AW AW AW AW AW AW AW AW
------------	--	---	--