



SYMBOL KEY	
Ⓢ	Smoke Detector
Ⓜ	Horn Strobe
Ⓟ	Pull Station
Ⓞ	Fire Extinguisher
ⓔ	Illuminated Exit Sign
ⓔ	Emergency Light Fixture

What is the specific use of this space?
 (found in IBC Table 1004.1.1)
 If multi-use space show area and
 calculate for most intense occupant load.

Both means of egress are now open to the existing vertical opening. Please see IBC Section 703.2.1 and show applicable code section(s) that allow an unprotected, unenclosed vertical opening.

Both means of egress are now open to the existing vertical opening. This altered stair was enclosed from the second floor to the exit discharge but is now open to the first floor. See IBC Section 708 Shaft Enclosures. Please show the code section(s) that allow two story open space and unenclosed stairs for the means of egress.

Occupant load for "meeting space" is based on assembly use and calculated differently than for the industrial spaces. Please adjust your calculations and show square foot floor areas for each type of use and the floor area allowance used in the occupant calculations (refer to IBC Section 1004).

2nd Floor Life Safety

SCALE: 1/4" = 1'-0"

