

OPERATIONS MATRIX		ACTIVATE ALARM INDICATOR	ACTIVATE AUDIBLE ALARM	ACTIVATE TROUBLE INDICATOR	ACTIVATE TROUBLE SIGNAL	TRANSMIT TROUBLE SIGNAL
FIRE ALARM INPUT	●	●	●	●	●	●
SMOKE DETECTORS	●	●	●	●	●	●
HEAT DETECTORS	●	●	●	●	●	●
PULL STATIONS	●	●	●	●	●	●
FIRE ALARM AC POWER FAIL	●	●	●	●	●	●
FIRE ALARM LOW BATTERY	●	●	●	●	●	●
OPEN CIRCUIT	●	●	●	●	●	●
GROUND FAULT	●	●	●	●	●	●
IMC SHORT CIRCUIT	●	●	●	●	●	●
LOSS OF AC TO BUILDING	●	●	●	●	●	●

- GENERAL NOTES:**
- THESE DRAWINGS ARE DIAGRAMMATIC. REFER TO THE ARCHITECTURAL DRAWINGS FOR EXACT DIMENSIONS.
  - INSTALLATION SHALL COMPLY WITH NEC, NFPA 72 AND ALL OTHER APPLICABLE CODES AS REQUIRED BY THE LOCAL AUTHORITY HAVING JURISDICTION.
  - WIRING DEPICTED ON THESE PLANS IS SCHEMATIC - ACTUAL WIRE LOCATIONS MAY DIFFER FROM THESE PLANS. WIRING SHALL BE PERFORMED AS ACTUAL BUILDING CONSTRUCTION CONDITIONS ALLOW AND TO MINIMIZE PENETRATIONS THROUGH AREA SEPARATION WALLS AND FIRE WALLS. THE USE OF A FACEWALL IS PERMITTED AS LONG AS NO 110V OR HIGHER VOLTAGE CABLES ARE IN THE SAME FACEWALL.
  - FIRE RATINGS SHALL BE MAINTAINED FOR ALL PENETRATIONS THROUGH FIRE-RATED CONSTRUCTION.
  - POWER FOR ALL FIRE ALARM PANELS, AND FIRE ALARM POWER SUPPLIES MUST BE PROVIDED BY A DEDICATED AC BRANCH CIRCUIT.
  - POWER-LIMITED AND NONPOWER-LIMITED CIRCUIT WIRING MUST REMAIN SEPARATED IN CABINET. ALL POWER-LIMITED CIRCUIT WIRING MUST REMAIN AT LEAST 0.25 AWAY FROM ANY NONPOWER-LIMITED CIRCUIT WIRING. FURTHERMORE, ALL POWER-LIMITED AND NONPOWER-LIMITED CIRCUIT WIRING MUST ENTER AND EXIT THE CABINET THROUGH DIFFERENT KNOCK OUTS AND/OR SEPARATE CONDUITS.
  - WHEN UTILIZING CLASS "A" CIRCUITS, SEPARATE OUTGOING AND RETURN CONDUCTORS OF CLASS "A" CIRCUITS BY A MINIMUM OF 12" WHERE RUN VERTICALLY AND 48" WHERE RUN HORIZONTALLY.
  - WHEN UTILIZING SHIELDED CABLE TIE SHIELDS THROUGH AND INSULATE AT EACH JUNCTION BOX. INSULATE AND TAPE BACK AT END.
  - ALL FIRE ALARM CABLING SHALL BE ACCEPTABLE TO THE FIRE ALARM EQUIPMENT MANUFACTURER FOR THE INTENDED PURPOSE.
  - SMOKE DETECTORS SHALL NOT BE INSTALLED UNTIL AFTER CONSTRUCTION CLEAN-UP IS COMPLETED AND FINAL.
  - LOCATE SMOKE DETECTORS A MINIMUM OF THREE (3) FEET FROM MECHANICAL DIFFUSERS. WALL-MOUNTED SMOKE DETECTORS SHALL BE LOCATED A MINIMUM OF 4" AND A MAXIMUM OF 12" FROM CEILING. CEILING-MOUNTED SMOKE DETECTORS SHALL BE MOUNTED ON CEILINGS AND NOT ON THE BOTTOMS OF BEAMS OR JOISTS.
  - PROVIDE SYNCHRONIZATION OF ALL VISUAL NOTIFICATION APPLIANCE CIRCUITS. PROVIDE ALL REQUIRED SYNC MODULES. PROVIDE A MULTI-SYNC MODE SLAVE CONNECTION BETWEEN ALL SYNC MODULES.
  - VERIFY ALL FIELD SELECTABLE AUDIBILITY SETTINGS OF NOTIFICATION APPLIANCES WITH FIRE ALARM CONTRACTOR.
  - UPON COMPLETION OF THE FIRE ALARM SYSTEM INSTALLATION AND PROGRAMMING, THE INSTALLING CONTRACTOR SHALL PERFORM FINAL TESTING OF THE ENTIRE SYSTEM, PER ALL APPLICABLE CODES, AND SHALL COORDINATE AND PERFORM A FINAL FIRE ALARM SYSTEM INSPECTION.
  - PROVIDE OFF-SITE MONITORING AS REQUIRED BY THE INTERNATIONAL FIRE CODE, SECTION 907.15 AND THE LOCAL AUTHORITY HAVING JURISDICTION.
  - INSTALLING CONTRACTOR SHALL, PHYSICALLY LABEL ALL INITIATING DEVICES AND NOTIFICATION APPLIANCE CIRCUIT END OF LINE (WHEN WIRING CLASS "B"). THESE LABELS SHALL BE IN PLACE PRIOR TO START-UP AND TESTING.

SYMBOL	DESCRIPTION	MOUNTING
FCP	FIRE ALARM CONTROL PANEL	WALL-TOP @ 66"
FPS	FIRE ALARM POWER SUPPLY	FIELD VERIFY
FSA	FIRE SYSTEM ANNUNCIATOR	WALL-TOP @ 66"
FSD	FIRE/SMOKE DAMPER	BY OTHERS
⊙	SMOKE DETECTOR	CEILING
⊙-	DUCT SMOKE DETECTOR	BY OTHERS
⊙	HEAT DETECTOR	CEILING
CM	ADDRESSABLE CONTROL MODULE	FIELD VERIFY
MM	ADDRESSABLE MONITOR MODULE	FIELD VERIFY
P	MANUAL PULL STATION	WALL @ 48"
R	CONTROL RELAY (MULTI-VOLTAGE)	FIELD VERIFY
RM	ADDRESSABLE RELAY MODULE	FIELD VERIFY
⊙	MAGNETIC DOOR HOLDER	FIELD VERIFY
⊙-	WATER FLOW SWITCH	BY OTHERS
⊙-	VALVE TAMPER SWITCH	BY OTHERS
⊙	BELL	BY OTHERS
⊙	CEILING MOUNT STROBE	FIELD VERIFY
⊙	CEILING MOUNT HORN / STROBE	FIELD VERIFY
⊙	CEILING MOUNT SPEAKER / STROBE	FIELD VERIFY
⊙	HORN	WALL @ 10'-0"
⊙	HORN / STROBE	WALL 80"-96"
⊙	SPEAKER / STROBE	WALL 80"-96"
⊙	SPEAKER	WALL 80"-96"
⊙	STROBE	WALL 80"-96"

ABBREVIATION	DESCRIPTION
E	EXISTING
G	WITH GUARD
R	PENDENT MOUNT
P	RESIDENTIAL (110V)
S	SCUMBER BASE
WP	WEATHER PROOF
⊙	END OF LINE RELAY
⊙	⊙
⊙	AMERICAN WIRE GAUGE
AWG	TWISTED PAIR
TWSP	TWISTED SHIELDED PAIR
FPLP	FIRE POWER LIMITED PLENUM
FPLR	FIRE POWER LIMITED RISER


REVISION	DESCRIPTION	DATE
0	ISSUED FOR REVIEW & APPROVAL	9/3/2014

**CUNNINGHAM**  
**Security Systems**  
 10 Prices Point Road, Yarmouth, Maine 04096  
 Office: 207.846.3350 • Fax: 207.846.6080


**MAINE ORTHOTIC LAB**  
**CORNER OF ST. JOHN STREET & PARK AVENUE**  
**PORTLAND, MAINE**  
**CALCS, DETAILS, LEGEND, NOTES, RISER**

DRAWN	JPB	UNICAD JOB #14518
CHECKED	WAYNE B. HANS	NCET 11 90496
DATE	9/3/2014	
REVISION	0	
SCALE	NONE	


**UNICAD** Inc.  
 578 W. 400th St.  
 Office: 801.865.6410  
 www.unicad.net  
 Fire Alarm Design & Drafting Services



MANUAL PULL STATION WIRING DETAIL  
 SCHEMATIC: NO SCALE




ADDRESSABLE SMOKE DETECTOR WIRING DETAIL  
 SCHEMATIC: NO SCALE



TYPICAL 2 WIRE STROBE WIRING DETAIL  
 SCHEMATIC: NO SCALE

FCP Battery Calculation		9/3/2014	
PROJECT NAME: 300 PARK AVENUE			
Required Standby Time:	24	Hours	
Required Alarm Time:	5	Minutes	
<b>Regulated Load in Standby</b>			
Device Type	Number of Devices	Current (Amps)	Total Current (Amps)
MS-9050UD Main Circuit Board	1	0.12000	= 0.12000
ANN-80 Remote Annunciator	1	0.01500	= 0.01500
H350-S Smoke Detectors	14	0.00030	= 0.00420
H350-12LX Pull Stations	7	0.00010	= 0.00070
EO-12LX Pull Stations	3	0.00023	= 0.00069
			0.14199
<b>Regulated Load in ALARM</b>			
Device Type	Number of Devices	Current (Amps)	Total Current (Amps)
MS-9050UD Main Circuit Board	1	0.20000	= 0.20000
ANN-80 Remote Annunciator	1	0.04000	= 0.04000
Max Alarm Draw - All Addressable Devices	1	0.40000	= 0.40000
MAC-1 (See voltage drop calcs for device quantity)	1	0.78000	= 0.78000
MAC-2	1	0.53000	= 0.53000
			1.95000
<b>Battery Requirements</b>			
Standby Load	Required Standby Time in Hours		
Current (Amps)	0.14199 X	24.00000	= 3.40776
Alarm Load	Required Alarm Time in Hours		
Current (Amps)	1.95000 X	0.08333	= 0.16250
Total Ampere Hours (before derating factor)			X 3.57026
Derating Factor			1.2
<b>TOTAL AMPERE HOURS REQUIRED</b>			4.28437
<b>BATTERIES TO BE PROVIDED (2 - 12v)</b>			7 AH

MAC Circuit Voltage Drop Calculation		9/3/2014	
PROJECT NAME: 300 PARK AVENUE			
Circuit Number: MAC-1			
Nominal System Voltage	20.4	Volts	
Minimum Device Voltage	18	Volts	
Wire Gauge for source to 1st device	14		
Wire Gauge for balance of circuit	14		
Resistance Per 1000	6.14		
Max Output Current	1.0	amps	
Total Circuit Current	0.780	amps	
<b>Circuit is within limits</b>			
Device	Distance previous device	Voltage at Device	Drop from source
1	0.176	20.20	0.20
2	0.176	20.15	0.25
3	0.107	20.13	0.27
4	0.079	20.09	0.31
5	0.176	20.05	0.35
6	0.066	20.04	0.36
Totals	0.780	1.30	
<b>MAC Circuit Voltage Drop Calculation</b>			
PROJECT NAME: 300 PARK AVENUE			
Circuit Number: MAC-2			
Nominal System Voltage	20.4	Volts	
Minimum Device Voltage	16	Volts	
Distance from source to 1st device	25		
Wire Gauge for balance of circuit	14		
Resistance Per 1000	6.14		
Max Output Current	1.0	amps	
Total Circuit Current	0.530	amps	
<b>Circuit is within limits</b>			
Device	Distance previous device	Voltage at Device	Drop from source
1	0.066	20.32	0.08
2	0.107	20.27	0.13
3	0.107	20.25	0.15
4	0.079	20.23	0.17
5	0.212	20.18	0.22
Totals	0.530	104	



WIRE NOTE:  
 VERIFY EXACT WIRE TYPE WITH FIRE ALARM CONTRACTOR BEFORE ORDERING.

FIRE ALARM RISER DIAGRAM  
 SCHEMATIC: NO SCALE