



SHEAR WALL SCHEDULE		
LEVEL	SHEATHING	HOLDOWNS
FIRST FLOOR	7/16" OSB ON BOTH SIDES OF WALL FASTENED W/ 8d @ 3" O.C.	HDU8-SDS2.5 W/ 7/8" O THRU BOLT
SECOND FLOOR	7/16" OSB ON BOTH SIDES OF WALL FASTENED W/ 8d @ 4" O.C.	MSTC66 EACH FACE EACH END
THIRD FLOOR	7/16" OSB ON ONE SIDE OF WALL FASTENED W/ 8d @ 4" O.C.	MSTC40 EACH FACE EACH END

NOTE: AT FIRST AND SECOND FLOOR OFFSET SHEATHING JOINTS ONTO DIFFERENT STUDS OR DOUBLE STUDS IF EDGE NAILED ON BOTH SIDES. -TYP.

THIRD FLOOR FRAMING PLAN
 NOTES:
 1. SEE SHEET S-1.0 FOR GENERAL STRUCTURAL NOTES
 SCALE 1/4"=1'-0"

FRAMING PLAN SYMBOLS KEY	
□	WOOD POST
⊗	NUMBER OF WOOD STUDS IN POST BELOW
A	COLUMN ABOVE THIS LEVEL
C	COLUMN CONTINUOUS THROUGH THIS LEVEL
←	TRUSS OR JOIST BEARING
⊥	FLUSH FRAMED JOIST BEARING WITH HANGER
⊥	WOOD STUD BEARING WALL BELOW
⊥	SHEAR WALL, SEE SCHEDULE -TYP
<E>	EXISTING FRAMING MEMBER
<N>	NEW FRAMING MEMBER
"X" T	NUMBER OF TRIM STUDS UNDER HEADER
"X" K	NUMBER OF KING STUDS ADJACENT TO HEADER