Avenue ve 04041 ark Park Av Maine 272 272 | ortland

12042

DRWN. Author Checker

1/4" = 1'-0"

ISSUE 04/26/2013

FIRST FLOOR DEMOLITION

SHEET

NORTH NORTH

AD101

to 4 inches minimum below the existing slab. Infill the slab with concrete as

removals with Structural, Mechanical and Electrical plans.

8. Refer to Civil, Plumbing, Mechanical, Structural and Electrical plans for additional demolition information. Coordinate the information on drawings and shall report any discrepancies to the Architect prior to proceeding with the work.

9. Removal of the materials as indicated shall be done without disturbing adjacent surfaces to remain or the current condition of the building elements.

10. The Owner shall remove furniture and other movable and/or fixed equipment prior to new work in any area, except for mechanical, electrical or minor work not requiring the Owner to completely vacate the premises. Notify the Owner of schedule for new work and extent of Owner removals necessary.

11. Remove all damaged and/or discarded building construction material from concealed spaces back to their original source. Prior to closing- or sealing-off concealed spaces, the Contractor shall allow for an inspection of components which will not be visible when the spaces have been sealed.

12. Cut trenches in existing concrete floors with no more than a 1:2 slope. Patch concrete to match adjacent thickness and finish prior to the installation of underlayment or new finishes.

13. Provide metal cover plates at all abandoned electrical devices, finished to match wall.

14. All demolition/removal debris is the property of the Contractor, unless noted otherwise.

15. The Contractor may replace salvaged items with new and identical materials only with the Architect's prior approval.

16. Remove all finishes including flooring, ceilings and base in all location U.N.O.

