



1. 15'x48", 18 ga. GALVANIZED STEEL VENTILATION HOOD.
2. ACCESSORIES INCLUDE (4) UL RATED VAPOR PROOF LIGHTS, (11) 20X16 GALV FILTERS, AND ENCLOSED GREASE CONTAINER.
3. FILTER SYSTEM IS COMPLETELY REMOVABLE FOR CLEANING.
4. EXTERNAL SEAMS AND JOINTS HAVE A LIQUID TIGHT, CONTINUOUS WELD.
5. HOODS BUILT TO NFPA 96 AND UL STANDARDS.
6. UL LISTED GREASE FILTERS INSTALLED AT A 45° ANGLE.
7. HOOD TO BE MOUNTED 3" FROM LIMITED COMBUSTIBLE WALL SURFACE.



NEW ENGLAND VENTILATION TECHNOLOGIES

SALVAGE BBO
PORTLAND, ME

SCALE NOT TO SCALE DATE 4-1-13 DRAWN BY RDD
KITCHEN VENTILATION HOOD DETAIL
SECTION, WALL CANOPY

DRAWING NUMBER
ENG\HOOD-DTL