NORRIS INC

PO Box 2551
2257 West Broadway
South Portland, ME 04106

1.800.370.3473
fax 207.879.0540

Reviewed for Code Compliance
Inspections Division
Approved with Conditions

Date: 06/19/13

5/17/13

Scope of Work: 919 Congress St.

Eastup Electric will be installing a new addressable fire alarm system to meet Code. The system will consist of a smoke detector over the fire alarm panel, 1 CO detector on each level, horn strobes and strobes as required and pull stations at the exits. The building is fully sprinkled and the sprinkler system will be monitored via the fire alarm panel. There will also be a kitchen hood system which will be monitored via the fire alarm panel.

The fire alarm panel will be located in the lower level mechanical room and there will be a remote annunciator located at the main entrance of the building.

The fire alarm panel will be monitored via a remote central station of the owner's choice. The final decision has not yet been made as to who will be doing the monitoring, but that information will be determined prior to final testing.

Norris Inc. will provide fire alarm equipment, submittal documents, fire alarm permits, final connections and testing per City of Portland requirements.