



LOWER LEVEL EGRESS PLAN
1/8" = 1'-0"

- FIRE EXTINGUISHER
- EXIT LIGHT
- EMERGENCY LIGHT

NEW 3'-0"X6'-8" 1 HOUR RATED EGRESS DOOR WITH CLOSER AND PANIC HARDWARE

LOWER LEVEL
Occupant Load:
 Dish Area, Kitchen 9 Occupants
 Office, 3 Occupants
 Accessory Storage, 6 Occupants
 Total 18 occupants
Egress Required:
 1 egress required: front door 36" and minimum stair width 44"
 One egress required per IBC table 1021.2

DATE:	2.21.2013
DRAWN BY:	BB
A-002	