



EXISTING 3/4  
MDF WOOD  
INFILL PANEL.  
MECHANICALLY  
FASTEN 2  
LAYERS OF 5/8  
TYP GYP ON  
UNIT SIDE OF  
PANEL. SEAL  
FULL PERIMETER  
WITH FIRE  
SEALANT.

REPLACE  
EXISTING LEAF  
WITH NEW DOOR  
MATCHING UNIT  
DOOR U1,  
PROVIDE NEW  
METAL  
THRESHOLD AND  
SMOKE  
GASKETS.